

**SPECIAL ORDERS SESSION  
WINNEBAGO COUNTY BOARD OF SUPERVISORS  
TUESDAY, JANUARY 3, 2023  
6:00 P.M.  
Winnebago County Courthouse – County Board Room  
415 Jackson Street, Oshkosh, Wisconsin**

**To join this video meeting via Zoom, use this link:**

<https://us02web.zoom.us/j/81753931025?pwd=TDFnZ2l3UHVaTStMazRPdXVEdkp3QT09>

**Passcode (if needed) – W1NNE**

**To join this meeting by telephone, dial (312) 626-6799. Enter the Meeting ID: 817 5393 1025**

**Passcode (if needed) –356762**

- \*Roll Call
- \*Pledge of Allegiance
- \*Invocation
- \*Adopt agenda

Time will be allowed for persons present to express their opinion on any resolution or ordinance that appears on the agenda, as well as, any matter over which this body has jurisdiction.

*Pursuant to Rules 6.4, 8.1 and 10.1 of the 2022-2024 Rules of the Winnebago County Board of Supervisors, the County Board Chairman shall limit all public comments to two (2) minutes.*

- \*Reports from Committees, Commissions & Boards
- \*County Board Chairman's Report

**AGENDA ITEMS**

1. *Resolution No. 155-012023 – Ratifying a Proclamation of a County Emergency Due to Extreme Winter Weather and Unplanned Staffing Shortages and Temporary Closing of the Day by Day Warming Shelter*  

*Submitted by:  
Chairman Thomas Egan*
2. Presentation on Winnebago County Social Media Policy – Mary Anne Mueller, Winnebago County Corporation Counsel; and Eric Rasmussen, Winnebago County Emergency Management Director
3. *Resolution No. 131-112022: Supporting Winnebago County Social Media Policy*  

*Submitted by:  
INFORMATION SYSTEMS COMMITTEE*
4. Presentation of 2023 – 2027 Capital Improvements Plan and 2023 Projects by Director of Finance Paul Kaiser, Director of Administration Mike Collard, Sheriff John Matz and Parks Director Adam Breest.

Respectfully submitted,  
Susan T. Ertmer  
Winnebago County Clerk  
(920) 232-3432

Upon request, provisions will be made for people with disabilities.

*(Times provided are estimates. Any item on the agenda may be taken up by the Board after 6:00 P.M.)*

**RESOLUTION: RATIFYING A PROCLAMATION OF A COUNTY EMERGENCY DUE TO EXTREME WINTER WEATHER AND UNPLANNED STAFFING SHORTAGES AND TEMPORARY CLOSING OF THE DAY BY DAY WARMING SHELTER**

**TO THE WINNEBAGO COUNTY BOARD OF SUPERVISORS:**

**WHEREAS**, on Monday, December 19, 2022, county officials were notified that the Day by Day Warming Shelter, a non-profit shelter in the City of Oshkosh, was facing significant staffing shortages and needed to temporarily close its overnight sheltering operation beginning December 21, 2022 and lasting through January 8, 2023; and

**WHEREAS**, on Tuesday, December 20, 2022, County Executive Jon Doemel signed an emergency proclamation pursuant to Wis. Stat §323.14(4)(b) that an imminent threat of disaster existed in Winnebago County because of the extreme winter weather and the temporary closing of the Day by Day Warming Shelter; and

**WHEREAS**, on Thursday, December 22, 2022, Governor Tony Evers issued an Energy Emergency to ensure energy fuel stability which was likely to occur due to demand for home heating increased by extreme cold weather conditions, and extreme cold temperatures; and

**WHEREAS**, Winter Storm Elliot resulted in significant snowfall, heavy winds, and blizzard conditions across the nation, state, and county, which would have likely resulted in significant injury and/or death to those unsheltered or living in homes without heat; and

**WHEREAS**, Winnebago County staff, with support from the City of Oshkosh, continues to operate a 24/7 emergency shelter at the location of the Day by Day Warming Shelter beginning Wednesday, December 21, 2022 which continues to shelter dozens of the county's residents; and

**WHEREAS**, the Interstate 41 causeway over Lake Butte des Morts and other county roadways suffered white-out conditions for several days as the wind blew snow across the roadways causing near 24/7 plowing operations for the county's highway department team; and

**WHEREAS**, while the weather has improved, the Day by Day Warming Shelter is still facing staffing shortages and needs more time to successfully train and equip newly hired staff to be successful; and

**WHEREAS**, County Executive Jon Doemel has requested a cross-department task force to work with the Day by Day Warming Shelter to plan for future needs and ensure continuity of operations.

**NOW, THEREFORE, BE IT RESOLVED** by the Winnebago County Board of Supervisors that pursuant to Wis. Stat § 323.11, it ratifies the emergency proclamation of County Executive Jon Doemel on December 20, 2022, and affirms an emergency existed within Winnebago County as a result of the bitter cold and snow brought by Winter Storm Elliot and that emergency concluded on December 29, 2022.

**BE IT FURTHER RESOLVED** by the Winnebago County Board of Supervisors that as a result of Day by Day Warming Shelter's planned temporary closure and potential for further operational challenges, pursuant to Wis. Stat §323.11, beginning on December 20, 2022, an emergency exists in the county and this body grants the County Executive, in consultation with the County Board Chairperson, general authority under Wis. Stat. §323.14(4) in order to be expedient for the health, safety, protection, and welfare of persons unsheltered, who would be otherwise left in the cold of the Wisconsin winter until the earlier of February 28, 2023, or the County Executive, in consultation with the County Board Chairperson, determines the staffing operations of the Day by Day Warming Shelter are stable.

43  
44 Fiscal Note: *Total costs are undetermined at this time; however, there is not an anticipated need for a budget transfer*  
45 *as many of the expenses can be handled under currently budgeted dollars. There are no long-term obligations for*  
46 *future budgets as a result of passing this resolution.*

47 Respectfully submitted by:  
48 **CHAIRMAN THOMAS J. EGAN**

49  
50 Vote Required for Passage: **Majority of those present**

51  
52 Approved by the Winnebago County Executive this \_\_\_\_ day of \_\_\_\_\_, 2023.

53  
54  
55 \_\_\_\_\_  
56 Jonathan D. Doemel  
Winnebago County Executive

# Agenda Item Report



**Winnebago County**  
*The Wave of the Future*

DATE: December 27, 2022

FROM: County Executive Jon Doemel and Human Services Director Bill Topel

RE: Ratifying a Proclamation of a County Emergency Due to Extreme Winter Weather and Unplanned Staffing Shortages and Temporary Closing of the Day by Day Warming Shelter

## **General Description:**

Ratifying an emergency proclamation for Winter Storm Elliot and issuing an emergency to assist the Day by Day Warming shelter with staffing and operational support.

## **Action Requested:**

Ratify the emergency proclamation for Winter Storm Elliot and extend the proclamation for the staffing operational shortages at Day by Day Warming Shelter until the earlier of February 28, 2023 or ended by the county executive.

## **Procedural Steps:**

This resolution is coming directly to the county board pursuant to Wisconsin Statutes 323.11 and 323.14(4)b. On December 20, 2022, County Executive Jon Doemel issued an emergency proclamation due to the temporarily closed Day by Day Shelter and the impending storm. The statutes require board action.

## **Background:**

On December 19, the county and city of Oshkosh were notified the Day by Day Warming Shelter located on High Avenue in Oshkosh was planning to close. The shelter did not have the required staff to operate in the evening. At the time, there was the threat of significant snow fall, heavy winds, cold temperatures, and blizzard conditions. There was no way the shelter was going to be able to operate 24/7 to ensure the safety of the shelter's clients and guests.

On December 20, county officials met with city officials to discuss how to prepare for the winter storm. The storm's effects were going to be exacerbated by the lack of an evening shelter. Further, the Christmas holiday was going to close many of the day hour warming locations. The weather also closed some of these warming locations.

On December 20, I issued an emergency proclamation which opened our emergency government plans. We then organized staffing of a 24/7 emergency shelter with county staff paid at a significant pay differential. In about an hour, all four-hour shifts were filled. In addition, the county employed several staff who had once been employed at the shelter.

The city provided two officers for the evening hours. Basic meals were provided by the jail. Renee Soroko, the deputy director of human services, was our incident commander and was able to coordinate a successful shelter with the DHS team.

As the weather event continued, we extended our 24/7 operations through Christmas. DHS staff called on-call backup staff to ensure enough staffing. The 24/7 operation was successful with little incident.

The plan is for the Day by Day Warming Shelter to be closed until January 9, 2023.



**Policy Discussion:**

State statutes allow the governing body of a local government to declare, through resolution, when the health and safety of people are at risk. We know Wisconsin winters are cold and at times, life threatening. We know there are about 30-40 individuals who sleep in cars or outdoors on a regular basis. Each of those lives are threatened when a shelter is closed or at risk of closing due to staffing.

After approval of this resolution, the county will be able to redeploy staff and use funds to assist in the staffing of the Day by Day Warming Shelter. Our expectation is that Day by Day works with the city, county, and state governments in an inter-agency and inter-department task force to identify a better operational plan for the shelter.

Between now and January 9, 2023, the county will fully operate the shelter. In the meantime, Day by Day will be hiring and training staff. They will also be reviewing operational plans to ensure future success. After January 9, the county will have the ability to redeploy staff to fill shifts as an effort to avoid future staffing shortage closures.

The resolution requires the county executive to consult with the county board chairperson. This ensures the county board is made aware of decisions required to ensure the safety and wellbeing of the population served by the shelter.

The emergency will end on February 28, 2023 unless ended sooner by the county executive. That date is not arbitrary as it is the February meeting of this body. This ensures the county and the shelter have enough time to get through the winter months without the need for an extension.

**Fiscal Impact:**

At this time a budget transfer is not necessary. The county is reallocating budgeted funds. Some of these funds are available due to staff vacancies in human services. Other funds are available for these types of uses. A better financial analysis will be available at the county board meeting on January 3. This resolution will not result in long-term obligations. All expenses are one-time. Some of the allocated Neighborhood Improvement Fund may be used to fund this emergency. Lastly, state and federal reimbursement through various agencies will be pursued.

**Attachments:**

Emergency Proclamation  
Resolution

# **PROCLAMATION OF A COUNTY EMERGENCY DUE TO EXTREME WINTER WEATHER AND UNPLANNED STAFFING SHORTAGES AND TEMPORARY CLOSING OF THE DAY BY DAY WARMING SHELTER**

**WHEREAS**, the Day by Day Warming Shelter is a non-profit organization located in the City of Oshkosh ("City") and is one of the primary organizations that provides temporary shelter for vulnerable adults within the City and Winnebago County ("County"); and

**WHEREAS**, due to unplanned staffing shortages, the Day by Day Warming Shelter will close from December 21, 2022 thru January 8, 2023 and will not provide any sheltering services during this time; and

**WHEREAS**, during this period, there is severe weather expected within the City and County with the National Weather Service reporting anticipated blizzard conditions and temperatures dropping below zero; and

**WHEREAS**, there is no known immediate alternative emergency housing available within the City or County during this period; and

**WHEREAS**, the immediate and unplanned closing of the Day by Day Warming Shelter in conjunction with the severe weather conditions threatens and negatively impacts the life, health, and safety of citizens of the City and County; and

**WHEREAS**, Winnebago County in cooperation with the City of Oshkosh desires to take action to protect its vulnerable citizens during this temporary period; and

**WHEREAS**, the potential for disaster exists which requires extraordinary measures to protect the health and well-being of the people of Winnebago County and the City of Oshkosh; and

**WHEREAS**, declaring an emergency will facilitate and expedite the use of resources to protect vulnerable persons from the impact of the closing of the Day by Day Warming Shelter during extreme weather conditions.

**NOW, THEREFORE, IT IS HEREBY PROCLAIMED** by the Winnebago County Executive pursuant to Wis. Stat §323.11 and §323.14(4)(b) that an imminent threat of a disaster exists in Winnebago County because of the extreme winter weather and the temporary closing of the Day by Day Warming Shelter.

**IT IS FURTHER PROCLAIMED AND ORDERED**, by the Winnebago County Executive in response to the temporary closing of the Day by Day Warming Shelter and the impending weather conditions, a State of Emergency is declared. During the existence of said emergency, support services for an emergency shelter established by Winnebago County will be available for those community members in need of shelter through January 10, 2023 or as may be extended by the Winnebago County Board of Supervisors.

**IT IS FURTHER PROCLAIMED AND ORDERED** by the Winnebago County Executive that during the existence of said emergency, the powers, functions, and duties of the Office of Emergency Management for Winnebago County shall be those prescribed by State law, and by ordinances and resolutions of the Winnebago County Board of Supervisors, as previously approved by the Winnebago County Board of Supervisors.

**IT IS FURTHER PROCLAIMED AND ORDERED** by the Winnebago County Executive, acting under the powers granted pursuant to §323.14(4)(b), Wis. Stats, that for and on behalf of the residents of Winnebago County, he will do

whatever is necessary and expedient to protect the health and well-being of Winnebago County, including the issuance of Administrative Orders and other directives as may be required.

Approved by the Winnebago County Executive this 20<sup>th</sup> day of December, 2022.

A handwritten signature in black ink, appearing to read 'Jonathan D. Doemel', is written over a horizontal line.

Jonathan D. Doemel  
Winnebago County Executive

131-112022

**RESOLUTION: Supporting Winnebago County Social Media Policy**

**TO THE WINNEBAGO COUNTY BOARD OF SUPERVISORS:**

**WHEREAS**, the Winnebago County Social Media Policy sets forth guidelines for the establishment and use of social media by Winnebago County for conveying information about Winnebago County and its events and activities; and

**WHEREAS**, this policy and procedure applies to all Winnebago County departments and Winnebago County Workforce Members contributing to websites, blogs, Wikis, social networks, virtual worlds, or any other kind of social media both on and off county websites; and

**WHEREAS**, for each social media profile approved for use by Winnebago County, the Department shall establish a list of authorized employees who may manage the social media profile; and

**WHEREAS**, Winnebago County must retain all social media content published by Winnebago County for the purposes of public records retention as may be required by applicable law; and

**WHEREAS**, social media will complement not replace Winnebago County's primary website.

**NOW, THEREFORE, BE IT RESOLVED** by the Winnebago County Board of Supervisors that it hereby supports the Winnebago County Social Media Policy enacted on September 1, 2022.

**Fiscal Note:** *No fiscal impact.*

Respectfully submitted by:

**INFORMATION SYSTEMS**

Committee Vote: **4-0**

Vote Required for Passage: **Majority of those Present**

Approved by the Winnebago County Executive this \_\_\_\_ day of \_\_\_\_\_, 2022.

\_\_\_\_\_  
Jonathan D. Doemel  
Winnebago County Executive

# Agenda Item Report



**Winnebago County**  
*The Wave of the Future*

DATE: October 4, 2022

FROM:

RE: Winnebago County Social Media Policy

## **General Description:**

Social Media is a method that many members of our community use to obtain information. Winnebago County encourages the use of social media outlets to further the goals of the County and the mission of its Departments where appropriate. The Winnebago County Social Media Policy provides standards and guidance to County Departments and personnel regarding the use of social media platforms for county business.

## **Action Requested:**

Motion for the adoption of the Winnebago County Social Media Policy.

## **Procedural Steps:**

Committee of Jurisdiction: INFORMATION SYSTEMS

Meeting date: 10-13-22

Action taken: \_\_\_\_\_APPROVED\_\_\_\_\_

Vote: \_\_\_\_\_4-0\_\_\_\_\_

County Board

Meeting date: 11-15-22

## **Background:**

Winnebago County has an overriding interest and expectation in deciding what is “announced” or “spoken” on behalf of the County through the use of social media.

Departments throughout Winnebago County have been using social media platforms to communicate with the public for over a decade with no County guidance or oversight. This policy establishes guidelines for the establishment and use of social media by the County for conveying information about the County and its events and activities. This policy also establishes guidance for employees acting in a personal capacity when using social media.

The County’s intent is to create a “government speech forum” or a “limited forum” devoted exclusively to the County’s postings to the public. Nothing in this policy shall be applied to prohibit or infringe upon any communication, speech, or expression that is protected or privileged under law. This includes speech and expression protected under state or federal constitutions as well as labor laws or other applicable laws.

## **Policy Discussion:**

Winnebago County Departments have been utilizing social media for more than a decade without any consistent standards. The goal of this policy is to provide guidance as Winnebago County continues to

utilize social media platforms to communicate and share information with the public. The policy is also intended to keep Winnebago County in compliance with record retention requirements as well as current case law that addresses social media use by Government agencies.

**Attachments:**

Winnebago County Social Media Policy

# **Winnebago County**

## **Social Media Policy**

*Effective September 1, 2022*

### **Introduction**

To address the fast-changing landscape of the Internet and the way residents communicate and obtain information online, Winnebago County Departments may consider participating in social media formats to reach a broader audience. Winnebago County encourages the use of social media outlets to further the goals of the County and the missions of its Departments where appropriate. This Policy provides standards and guidance to county departments and personnel regarding the use of social media platforms for county business.

### **Policy**

#### **1. Purpose.**

- 1.1** Winnebago County (the “County”) has an overriding interest and expectation in deciding what is “announced” or “spoken” on behalf of the County through the use of social media. This policy establishes guidelines for the establishment and use of social media by the County for conveying information about the County and its events and activities. This policy also establishes guidance for employees acting in a personal capacity when using social media.

The County’s intent is to create a “government speech forum” or a “limited forum” devoted exclusively to the County’s postings to the public. Nothing in this policy shall be applied to prohibit or infringe upon any communication, speech or expression that is protected or privileged under law. This includes speech and expression protected under state or federal constitutions as well as labor laws or other applicable laws.

#### **2. The County's Website.**

- 2.1** The County’s website ([www.winnebagocountywi.gov](http://www.winnebagocountywi.gov)) is the County’s primary and predominant internet presence. All of the County’s website content and social media sites that are posted by departments and offices will be subject to approval by the Department Head or designee. Social media use should complement rather than replace the County’s primary website. Only employees authorized by the Department Head are authorized to post content on the County’s website.

#### **3. Scope.**

- 3.1** This policy and procedure applies to all departments and County Workforce Members of Winnebago County contributing to websites, blogs, Wikis, social networks, virtual worlds, or any other kind of social media both on and off County websites.

#### **4. Definitions.**

- 4.1** Social Media. Refers to content created by individuals with the use of various technologies for the purpose of information sharing through the Internet. Examples of social media are Blogs, Discussion Forums, Social Networking websites, Photo-sharing websites, Video-sharing websites, Wikis, and more.
- 4.2** Accounts:
- 4.2.1** Employee Account. This is a workforce member user account created and managed by Winnebago County. It is in the format: @winnebagocountywi.gov. It is also the workforce members official email address.
  - 4.2.2** External County Account. This is an account with an external server or service, such as a Gmail email account associated with and required to perform an official county function.
  - 4.2.3** Personal Account. This is an account that is external of Winnebago County, independent of employment with Winnebago County. It is not an official account.
  - 4.2.4** Shared Account. This is an account that includes shared access to various workforce members.
- 4.3** County Workforce Members. Includes, but is not limited to, employees, contractors, consultants, volunteers, 3rd party affiliates, or any entity doing work on the behalf of Winnebago County or using information systems owned, operated, or leased by Winnebago County.
- 4.4** Blog (short for web log). A type of website with regular diary style entries commonly displayed in reverse-chronological order. Entries usually contain commentary, descriptions of events, or other material such as graphics or video. Blog readers usually have the ability to leave comments.
- 4.5** Discussion Forum. An online discussion site where individuals can discuss topics by leaving messages and receiving responses. Many topics on forums can include questions, comparisons, polls of opinion, and debates.
- 4.6** Social Networking Websites. Focuses on the building of social networks or social relations among people. Social networking sites allow users to interact, share ideas, activities, events, and interests with people within their individual networks. Examples include Facebook, MySpace, Twitter, LinkedIn, etc.
- 4.7** Instant Messaging. Any tool used for text communications between county workforce members and/or the public. Examples include, but are not limited to, Microsoft Skype, Facebook Messenger, and Microsoft TEAMS.
- 4.8** RSS. Short for Really Simple Syndication. Allows subscribers to receive content from blogs and other social media sites and have it delivered



through a feed.

- 4.9** Podcasts. Audio or video content that can be downloaded automatically through a subscription to a website so you can view or listen offline.
- 4.10** Wiki. A website that allows the easy creation and editing of a number of interlinked web pages. They are often used to create collaborative websites, to power community websites, for personal note taking, and in corporate intranets.
- 4.11** Website. Servers, software and services necessary to present content (pages) to people using an internet web browser. Some websites are categorized as county managed or not county managed.
- 4.12** Public Event. A non-program specific event open to the general public which would include public meetings.

## **5. Social Media Posting.**

As a public entity, the County must abide by certain standards to serve all constituents in a civil and unbiased manner. Only the County Communication Team is authorized to administer and manage posts to the Winnebago County, WI Government official page. Only employees authorized by the Department Head may post content on their respective official County Department social media profile. The Information Technology Department will maintain a list of social media profiles approved for use by departments. Each Department using social media platforms shall maintain a list of authorized employees responsible for communicating the County's business on their Department's page. Any social media profiles used by the County are the property of the County and not the property of an employee or other party. Authorized employees will inform the Information Technology Department of any administrative changes to existing social media profiles.

- 5.1** For each social media profile approved for use by the County, the Department shall establish a list of authorized employees who may manage the social media profile.
- 5.2** Authorized employees representing the County on social media must conduct themselves at all times as professional and dignified representatives of the County and in accordance with all policies, directives, and professional expectations.
- 5.3** Employees posting content on behalf of the County must follow these guiding principles:
  - 5.3.1** Communications must be consistent with the goals, branding, mission, vision, and values of the County.
  - 5.3.2** Communications must be factual and accurate and not reflect opinions or biases.
  - 5.3.3** Communicate meaningful, respectful entries that are on topic while also recognizing that postings are widely accessible and not easily retractable.

- 5.3.4 Communications must be written in plain business English with proper grammar and vocabulary, and should avoid acronyms and jargon.
- 5.3.5 Communications must comply with policy, directives, professional expectations, and respect for privacy, confidentiality, and applicable legal guidelines for external communication.
- 5.3.6 Ensure that legal right exists to publish all materials, including photos and articles, and comply with all trademark, copyright, fair use, disclosure of processes and methodologies, confidentiality, and financial disclosure laws.
- 5.3.7 If identifying yourself, then maintain transparency by using your real name and job title, and by being clear about your role regarding the subject. Write and post only about your area of expertise. Remember that your postings are your responsibility.
- 5.3.8 Communications must never be for political purposes or in support of or opposition to political campaigns or ballot measures.
- 5.3.9 Communications must never be for purposes of private business activity or commerce, or for personal motivation or sharing of personal opinion or commentary.
- 5.3.10 Communications must not promote, foster, or perpetuate discrimination, harassment, or retaliation on the basis of race, creed, color, age, religion, gender, marital status, national origin, disability, or sexual orientation, or other protected status.
- 5.3.11 Communications must not compromise the safety or security of the public, public systems, or public services.
- 5.3.12 Communications must protect the privacy of clients and others in the County. Personally, identifiable information such as social security numbers, phone numbers, addresses, or email addresses shall not be included in communications. You must also protect the privacy of any sensitive and confidential information the County holds.
- 5.3.13 If posting a picture or video of an adult, or minor child, the individual, or parent/legal guardian must consent to the use of their image on the social media site, unless the picture or video was taken at a public event.

**5.4** Appropriate time spent on updating social media sites should be discussed between the employee and supervisor, and should not interfere with completion of other job duties. Time spent updating social media outside of normal work hours must be approved by the employee's Department Head or supervisor.

**5.5** The general position of the County is to use social media that promotes one-way communication from the County to the public. Social media platforms are reserved for government speech to allow County officials and Departments to post notices and information. As such, "commenting," "liking," or "non-liking" of a **post or comment** by authorized employees on behalf of the County is not permitted except in the following limited circumstances, the employee's name and title should be made available in the responsive comment:

**5.5.1** An employee may respond to a comment when the employee is

providing contact information to the commenter to seek or provide further information.

**5.5.2** An employee may respond to a comment or post to direct the poster to the County's website or to a previous social media post by the County.

**5.5.3** An employee may respond to a comment to provide a guidance or a technical answer to a question.

**5.6** If a comment or post demonstrates or incites unlawful behavior, the authorized employee may notify law enforcement authorities.

**5.7** A post, like, or comment by a member of the public on any County social media profile is the opinion of the commentator or poster only. Publication of a user's post, a like, or a comment does not imply endorsement of, or agreement by, the County or reflect the opinions or policies of the County. The County assumes no liability for any comment, like, or post made by another person.

**5.8** The County should not deny access to the County's social media profile ~~to from~~ any individual who violates the County's social media policy. The social media provider may, relying ~~on~~ their terms and conditions and their discretion, block a user or remove content in violation of the terms and conditions, and nothing herein restrains the social media provider from such actions.

**5.9** The nature of social networking promotes a great deal of interactivity, whereby users or organizations "like" or "follow" each other online. Official County social media sites may "like" or "follow" the **social media sites** of local, state, and federal government organizations, generally recognized community and/or not-for-profit organizations, and organizations that provide public safety, promote tourism, industry, and economic welfare within the community, and businesses located within Winnebago County.

**5.10** It is the responsibility of the department to establish, publish, and update their pages on social media websites. It is the responsibility of the department to ensure that information is accurate and up-to-date. Inactive or unused social media sites may be terminated or merged by the County Communication Team and the Department Head responsible for the account. Coordination to provide record retention back-ups by the Information Technology Department must be completed prior to termination or merging.

## **6. Record Retention.**

**6.1** The County must retain all social media content published by the County for the purposes of public records retention as may be required by applicable law. Records required to be maintained pursuant to a relevant records retention schedule for the required retention period in a format that preserves the integrity of the record and is accessible. Any content removed by the County based on these guidelines must be retained in accordance with the applicable retention schedule including the time, date and identity of the poster, when available. The Information Technology Department will retain appropriate public records. Any Department wishing to establish a new social media site, must notify Information Technology prior to establishment.

## **7. Open Meetings Law Compliance.**

- 7.1** All conduct by officials serving on a governmental body must comply with Wisconsin's Open Meetings Law. Officials should refrain from discussing business or action of the governmental body with one another while using social media. Authorized employees publishing on the County's social media profile should not engage officials serving on a governmental body when engaging in the County's social media activity.

## **8. Personal Use of Social Media.**

- 8.1** Like other members of the community, employees may use social media profiles not belonging to the County for the employee's personal social media purposes. The County values employees' First Amendment right to communicate on their personal social media accounts; however, it is important that employees are aware that there are limitations to this right. It is also important employees are aware that most uses of personal social media are still part of the public domain regardless of privacy settings, as content posted to the internet is easily replicated and published despite attempted privacy measures an employee might otherwise undertake.
- 8.2** An employee's personal social media profile or use must remain personal in nature and not be used to share the County's official government positions or views. In addition, employees are prohibited from using their County e-mail account, login, or passwords in conjunction with a personal social media profile. Regardless of whether an employee identifies on a personal social media account that the employee works for the County, employment with the County is public record and members of the public may associate the employee with the County. As a result, members of the public may associate an employee's speech on a private social media page as attributable to the County. For these reasons, employees must exercise care when posting and commenting on social media, as personal views can be tied back to employment with County.
- 8.3** Employees posting personal content on social media must follow these guiding principles:
- 8.3.1** When commenting or posting on matters pertaining to the County, the employee must make clear to other persons that the employee is speaking as a private citizen and not as an employee of the County.
  - 8.3.2** Personal activity must comport with the County's policies, directives and expectations.
  - 8.3.3** Personal activity is the personal responsibility of the employee, including the consequences that flow from such activity.
- 8.4** Nothing in this policy is meant to prevent an employee from exercising his or her right to make a complaint of unlawful discrimination or other workplace misconduct through the proper processes, to engage in lawful protected concerted activity, or to express a personal opinion on a matter of public concern which may be balanced against the interests of the County.

## **9. Winnebago County Social Media Policy (for posting on social media sites).**

- 9.1** The following Policy Statement shall be displayed on all County social media pages:

*The purpose of this site is to present matters of public interest to Winnebago County residents, businesses, visitors and other interested parties. A comment posted by the member of the public on any Winnebago County social media site is the opinion of the commenter only and publication of a public comment does not imply endorsement, nor reflect the opinions or policies of, Winnebago County.*

*This forum is NOT monitored at all times but is primarily monitored during business hours.*

*Do NOT use this forum to report emergency situations or time-sensitive issues.*

*All content of this page including comments is subject to public records law. When posting, please remember that if your comment or post demonstrates or incites unlawful behavior, it may be referred to law enforcement authorities. The social media provider may, relying on their terms and conditions and their discretion, block a user or remove content in violation of the terms and conditions.*

**10. Violations of this Policy.**

- 10.1** Social media administrators may face disciplinary action up to and including termination for using social media in a manner that violates County policies. Information posted on social media sites can be used by the County as evidence in disciplinary actions. Public social media content may be subject to legal discovery including subpoenas in legal proceedings.

**CERTIFICATION**

I have read and understand the Winnebago County Social Media Policy and I agree to abide by these policies.

---

Printed Name

---

Signature



---

Date





# Executive Capital Improvement Plan 2023







# Executive Capital Improvement Plan 2023

## Table of Contents

Executive CIP Summary 2023 Projects	4
Source & Use of Funds	5
Taxiway Alpha (A) Reconstruction - Final Phase	6-7
Replace Plow Truck	8-10
Courthouse Fourth Floor Ceiling Repairs	11-14
JP Coughlin Center Boiler Replacement	15
Courthouse Fall Protection Install	16
Facility Masonry Maintenance Program	17-20
Neenah Human Services Boiler Replacement	21
Park View Fire Alarm Replacement	22
Roof Replacement Program	23-25
CTH F (Omro - CTH D)	26-27
CTH JJ (CTH CB to STH 76)	28-29
CTH P (Midway Road - STH 47)	30-31
Highway Department Office and Shop Modernization	32-34
CTH II (STH 76 to 45 to N CTY Line Road	35-37
Repair and improvement of the Waukau Creek Dam	38-42
Jail Wiring and Camera	43-47
Dispatch Console Work Station Replacement	48-50
UWO-FOX, Barlow Planetarium Updates	51-52
UWO-FOX, Food Service and Union Facilities	53-55
UWO-FOX, HVAC Controls replacement for Admin and 1300	56
UWO Fox Cities - Library Roof Replacement	57
UWO-FOX, Replace Science Wing Windows	58
Executive CIP 5 Year Plan 2023-2027	59-60
Projects Removed from the Executive Capital Improvement Plan	61
OPEN Capital Project Status Report	62-67
Outstanding Indebteness - All (Includes Solid Waste & Highway)	68
Future Financing Plan 2022-2026	69
Debt Service Tax Rate 2022-2036	70





# Executive Capital Improvement Plan 2023

## Executive Capital Improvement Plan 2023-2027

The 2023 - 2027 Executive Capital Improvements Plan is submitted to the County Board for its review. These projects included in the Capital Improvement Plan for funding in 2023 will be included in a resolution expected to be submitted to the Board for approval in February, 2023.

### CAPITAL PROJECT DEFINITION

A **capital project** is a long-term project to build, improve, maintain, or develop a capital asset. This type of project involves a significant and consistent flow of investment that exceeds \$100,000. **Capital assets** include land, buildings, machinery, vehicles, computer equipment, etc.

### GENERAL

This document is intended to serve the following purposes:

- 1) Identify proposed projects within the planning horizon from 2023-2027 that would allocate, define and review limited resources.
- 2) Provide continuity in financial decisions linking long-term planning and approving to the annual budget process.
- 3) Assure a coordinated county-wide approach to setting priorities.
- 4) identify existing debt service requirements so that these are considered in the formulation of annual bonding proposals.
- 5) Identify a proposal for the use of undesignated general fund balance current and long-term projects.

### SOLICITATION OF PROJECT REQUESTS

Projects have been identified through communication of project request forms from department heads. Department heads were asked to review previously identified projects and resubmit those or new projects. Project request forms were submitted for each. With this information, a comprehensive list of projects has been assembled and evaluated under the leadership and direction of the County Executive, Director of Administration and Director of Finance.

### TECHNICAL REVIEW

The first step of the review consisted of a technical review. This was to insure that:

- 1) Request forms were properly prepared and classified as to project type.
- 2) All project costs and sources of funds were appropriately identified.
- 3) All additional information required for a complete evaluation of projects has been obtained.

### PROJECT EVALUATION / DOCUMENT ASSEMBLY

Subsequent to technical review, a preliminary document was assembled and presented to the County Executive for recommendations, revisions, and instructions. This document is the culmination of that process. The Executive Capital Improvements Plan will be updated on an annual basis to assure that all projects are identified, priorities established and annual bonding and application of undesignated general fund balance is held to an acceptable level.



# Executive Capital Improvement Plan 2023

## Cost of Capital Improvement Plan Projects

Department	Project Description	Resolution	Prior		2023 Years Cost		Future Years		Total
		Number	Approved	Spent	County	Other Funding	County	Other Funding	
Airport	Taxiway Alpha (A) Reconstruction - Final Phase				15,000	285,000	175,000	3,325,000	3,800,000
Airport	Replace Plow Truck				140,000				140,000
Facilities	Courthouse Fourth Floor Ceiling Repairs				155,000				155,000
Facilities	JP Coughlin Center Boiler Replacement				10,000		150,000		160,000
Facilities	Courthouse Fall Protection Install				125,000				125,000
Facilities	Facility Masonry Maintenance Program				162,000		615,000		777,000
Facilities	Neenah Human Services Boiler Replacement				10,000		150,000		160,000
Facilities	Park View Fire Alarm Replacement				113,640				113,640
Facilities	Roof Replacement Program	154-042021	227,000	139,347	275,624		917,816		1,193,440
Highway	CTH F (Omro - CTH D)				1,626,818				1,626,818
Highway	CTH JJ (CTH CB to STH 76)				929,600				929,600
Highway	CTH P (Midway Road - STH 47)	114-012021	780,000	24,149	150,000		1,229,700	5,270,300	6,650,000
Highway	Highway Department Office and Shop Modernization				2,810,000		2,500,000		5,310,000
Highway	CTH II (USH 45 - North Co Line)				1,886,365	450,641			2,337,006
Parks	Repair and improvement of the Waukau Creek Dam				230,000		750,000	750,000	1,730,000
Sheriff	Jail Wiring and Camera				350,000				350,000
Sheriff	Dispatch Console Work Station Replacement				260,000				260,000
UW Fox Cities	UWO-FOX, Barlow Planetarium Updates	115-102022	12,000	-	77,500	77,500			155,000
UW Fox Cities	UWO-FOX, Food Service and Union Facilities	42-042022	350,000	-	2,209,000	2,209,000			4,418,000
UW Fox Cities	UWO-FOX, HVAC Controls replacement for Admin and 1300				44,165	44,165			88,330
UW Fox Cities	UWO Fox Cities - Library Roof Replacement				175,000	175,000			350,000
UW Fox Cities	UWO-FOX, Replace Science Wing Windows				232,050	232,050			464,100
<b>Total Cost</b>			<b>1,369,000</b>	<b>163,496</b>	<b>11,986,762</b>	<b>3,473,356</b>	<b>6,487,516</b>	<b>9,345,300</b>	<b>31,292,934</b>

\*\*\*NOTE\*\*\* Decision on Which Project to keep in Current Year and the other to move to Future Year to stay under \$10M of CIP per Executive. If HWY Bldg selected need to add back removed Mold Remediation Page 61. \$600K

Other Projects Approved or Designated as ARPA									
Airport	Replace Rapid Intervention Vehicle (RIV) - ARFF				300,000				300,000
Facilities	Expo Center Emergency Generator Install				80,000		720,000		800,000
Information Systems	Redundant Fiber Loop - installation				542,600	212,400			755,000
Sheriff	Subscriber Unit Radios				1,800,000		760,000		2,560,000
Parks	Automated Pay Stations - Boat Landings				120,000				120,000
Facilities	980 Residential Facility Construction			-	1,068,427				1,068,427
Facilities	Sheriff Evidence Storage and Coroner Morgue Boulding			2,500	1,397,050		430,530		1,830,080
Parks	Grundman Boat Landing Improvement Project			54,824	678,363	1,243,313			1,976,500
ARPA Funding									
Already Approved									



# Executive Capital Improvement Plan 2023

## PROJECT DETAIL - 2023 BONDING (Borrowing) AND USE OF UNDESIGNATED GENERAL FUND BALANCE

This section presents detailed information on each of the projects included in the 2023 Executive Capital Improvement Plan with information on each proposed project being shown in the following format:

A. Anticipated Project Costs & Sources of Funds:

This refers to the financial requirements of the project to be met through the 2023 bond issue and any application of undesignated general fund balance.

B. Description of Project Plan & Justification:

This section provides a narrative description of the projects, their justification, and other descriptive materials such as maps or diagrams.

C. Supporting Documentation & Presentations:

This section shows pictures and/or drawings representing work to completed

## PROJECT DESCRIPTIONS – PROJECTS REQUIRING FUNDING DURING 2023

Projects and descriptions start on next page.



# Executive Capital Improvement Plan 2023

Project Name --->> Airport - TWY A Reconstruction - Final Phase								
ANTICIPATED PROJECT COSTS AND SOURCES OF FUNDS:								
	Prior years	2023	2024	2025	2026	2027	Beyond	Total
<b>PROJECT COSTS</b>								
Planning, Design,								-
Engineering		300,000						300,000
Land Purchase								-
Construction								-
Equipment			3,500,000					3,500,000
Other								-
TOTAL	-	300,000	3,500,000	-	-	-	-	3,800,000
<b>PROJECT FUNDS</b>								
County Funding		15,000	175,000					190,000
Outside funding		285,000	3,325,000					3,610,000
Operating Tax Levy								-
Previous bonding								-
TOTAL	-	300,000	3,500,000	-	-	-	-	3,800,000

## Project Description:

TWY A has been reconstructed, in 2020, from the far south end of the airfield to an area just south of TWY A1. This project will complete the reconstruction of the last remaining portion of TWY A between TWY A1 and the south side of RWY 9/27. The concrete in this section of Taxiway was built in 1967 which makes it over 55 years old. It has outlived it's useful life and requires replacement.

## Relationship to Other Projects:

This project is not related to any other project.

## Justification & Alternatives Considered

This project is dependent on the outcome of the Airport's Master Plan Update, scheduled to conclude in early 2023. After the finalization of the Master Plan, the exact configuration of the runways and taxiways in the vicinity of this project will be approved by FAA, which will allow this final portion of TWY A to be designed in 2023 and reconstructed in 2024 pending grant funding authorization from FAA and WI Bureau of Aeronautics (BOA).





# Executive Capital Improvement Plan 2023

Project Name: Airport - TWY A Reconstruction – Final Phase





# Executive Capital Improvement Plan 2023

Project Name --->> Airport - Replace Plow Truck								
ANTICIPATED PROJECT COSTS AND SOURCES OF FUNDS:								
	Prior years	2023	2024	2025	2026	2027	Beyond	Total
<b>PROJECT COST'S</b>								
Planning, Design, Engineering								-
Land Purchase								-
Construction								-
Equipment		140,000						140,000
Other								-
TOTAL	-	140,000	-	-	-	-	-	140,000
<b>PROJECT FUNDS</b>								
County Funding		140,000						140,000
Outside funding								-
Operating Tax Levy								-
Previous bonding								-
TOTAL	-	140,000	-	-	-	-	-	140,000

## Project Description:

Both current vehicles this will replace are 2WD and have multiple limitations to their ability to carry out various needed functions. This vehicle will be 4WD and have the capabilities of both replaced vehicles in one truck. The 1979 GMC Brigadier is over 40 years old and is simply too costly to maintain and has very limited availability on replacement parts. The second vehicle this is replacing will be eliminated in the fleet, thereby reducing the overall equipment fleet by one.

## Relationship to Other Projects:

This project is not related to any other project.

## Justification & Alternatives Considered

Both current vehicles this will replace are 2WD and have multiple limitations to their ability to carry out various needed functions. This vehicle will be 4WD and have the capabilities of both replaced vehicles in one truck. The 1979 GMC Brigadier is over 40 years old and is simply too costly to maintain and has very limited availability on replacement parts. The second vehicle this is replacing will be eliminated in the fleet, thereby reducing the overall equipment fleet by one.





# Executive Capital Improvement Plan 2023

2000 Chevrolet Silverado 3500 HD



1980 GMC Brigadier Dump Truck





# Executive Capital Improvement Plan 2023



Here's a quick overview of specs on a new plow truck to replace #54 (1980 Dump Truck) and #8 (2000 Plow Truck) We're looking for something to fit in between the size of the two of these yet perform both tasks sufficiently. Summer use for landscaping and hauling dirt/gravel, winter use for snow plowing and spreading salt in the off-airport parking lots. Ford Makes an F600, which allows larger weight capacity in a smaller chassis. I'll attach a link of a similarly priced truck along with pictures of the two of our trucks. Roughly \$110,000 equipped, but figure another \$10,000-\$15,000 after the fact for lights, radios, and yellow paint and decals.

2022 Ford F-600, 2D Standard Cab, 397 Amp Alternators, Air Conditioning, AM/FM Stereo w/MP3 Player, Folding Trailer Tow Mirrors w/Power Heated Glass, GVWR: 22,000 lbs Payload Package, HD Vinyl 40/20/40 Split Bench Seat, Limited Slip w/4.88 Axle Ratio, MyKey, Order Code 680A, Power Equipment Group, Power Front Side Windows, Power Locks, Remote Keyless Entry, Steering Wheel-Mounted Cruise Control, SYNC Communications & Entertainment System, Trailer Brake Controller, Upfitter Interface Module, Utility Lighting System, Variably Intermittent Wipers, XL Value Package.

Oxford White 2022 Ford F-600 XL 4WD Power Stroke 6.7L V8 DI 32V OHV Turbodiesel 2D Standard Cab 14' Galion Steel Dump, Western 8' to 10' WideOut Plow





# Executive Capital Improvement Plan 2023

Project Name ----> Facilities - Courthouse Fourth Floor Ceiling Repair								
ANTICIPATED PROJECT COSTS AND SOURCES OF FUNDS:								
	Prior years	2023	2024	2025	2026	2027	Beyond	Total
<b>PROJECT COST'S</b>								
Planning, Design, Engineering		5,000						5,000
Land Purchase								-
Construction		150,000						150,000
Equipment								-
Other								-
TOTAL	-	155,000	-	-	-	-	-	155,000
<b>PROJECT FUNDS</b>								
County Funding		155,000						155,000
Outside funding								-
Operating Tax Levy								-
Previous bonding								-
TOTAL	-	155,000	-	-	-	-	-	155,000

## **Project Description:**

This project is to repair the ceiling in the Courthouse 4th Floor Courtroom. The ceiling has been damaged by water leaking from the air conditioning unit in the 4th floor attic. Additionally the acoustical tiles are beginning to sag as the adhesive applied in 1938 has deteriorated. This project was originally developed and planned to be accomplished in the 2018 operational budget. The costs returned through bidding exceeded \$100,000. There was insufficient funding in the operational budget to accomplish the work. The project was then included in the Department relocation project for the Courthouse. The costs for the that entire project exceeded the project estimate. The ceiling work was deferred again. As a result it is being moved to the Capital budget.

## **Relationship to Other Projects:**

This project is not related to any other project.


## **Justification & Alternatives Considered**

There are really only two alternatives. Complete the repairs or do nothing. If nothing is done the ceiling will continue to deteriorate and eventually acoustical ceiling tiles will start falling potentially causing injury.



# Executive Capital Improvement Plan 2023

**Project Name: Facilities - Courthouse 4<sup>th</sup> Floor Ceiling Repair**





# Executive Capital Improvement Plan 2023

Project Name: Facilities - Courthouse 4<sup>th</sup> Floor Ceiling Repair


## LIGHTING PLAN



EXISTING POWER  
DEVICE

NEW LIGHT  
FIXTURE IN  
EXISTING  
LOCATION

EXISTING  
CEILING FAN

EXISTING COMM  
DEVICE



 KONTEXT architects building relationships 300 East Bayshore - Madison, WI	
 Winnebago County 1221 Knapp Street Oshkosh, WI 54902	
HISTORICALLY SIGNIFICANT CEILING REPAIR WINNEBAGO COUNTY COURTHOUSE BRANCH II / COUNTY BOARDROOM	
DATE: 4/11/2023 DRAWN BY: JACOBSON ST PROJECT NO: A101	
PROJECT: LIGHTING PLAN	
REVISIONS	
NO. DESCRIPTION	
1.000	
2.000	
3.000	
4.000	
5.000	
6.000	
7.000	
8.000	
9.000	
10.000	
11.000	
12.000	
13.000	
14.000	
15.000	
16.000	
17.000	
18.000	
19.000	
20.000	
21.000	
22.000	
23.000	
24.000	
25.000	
26.000	
27.000	
28.000	
29.000	
30.000	
31.000	
32.000	
33.000	
34.000	
35.000	
36.000	
37.000	
38.000	
39.000	
40.000	
41.000	
42.000	
43.000	
44.000	
45.000	
46.000	
47.000	
48.000	
49.000	
50.000	
51.000	
52.000	
53.000	
54.000	
55.000	
56.000	
57.000	
58.000	
59.000	
60.000	
61.000	
62.000	
63.000	
64.000	
65.000	
66.000	
67.000	
68.000	
69.000	
70.000	
71.000	
72.000	
73.000	
74.000	
75.000	
76.000	
77.000	
78.000	
79.000	
80.000	
81.000	
82.000	
83.000	
84.000	
85.000	
86.000	
87.000	
88.000	
89.000	
90.000	
91.000	
92.000	
93.000	
94.000	
95.000	
96.000	
97.000	
98.000	
99.000	
100.000	
101.000	
102.000	
103.000	
104.000	
105.000	
106.000	
107.000	
108.000	
109.000	
110.000	
111.000	
112.000	
113.000	
114.000	
115.000	
116.000	
117.000	
118.000	
119.000	
120.000	
121.000	
122.000	
123.000	
124.000	
125.000	
126.000	
127.000	
128.000	
129.000	
130.000	
131.000	
132.000	
133.000	
134.000	
135.000	
136.000	
137.000	
138.000	
139.000	
140.000	
141.000	
142.000	
143.000	
144.000	
145.000	
146.000	
147.000	
148.000	
149.000	
150.000	
151.000	
152.000	
153.000	
154.000	
155.000	
156.000	
157.000	
158.000	
159.000	
160.000	
161.000	
162.000	
163.000	
164.000	
165.000	
166.000	
167.000	
168.000	
169.000	
170.000	
171.000	
172.000	
173.000	
174.000	
175.000	
176.000	
177.000	
178.000	
179.000	
180.000	
181.000	
182.000	
183.000	
184.000	
185.000	
186.000	
187.000	
188.000	
189.000	
190.000	
191.000	
192.000	
193.000	
194.000	
195.000	
196.000	
197.000	
198.000	
199.000	
200.000	
201.000	
202.000	
203.000	
204.000	
205.000	
206.000	
207.000	
208.000	
209.000	
210.000	
211.000	
212.000	
213.000	
214.000	
215.000	
216.000	
217.000	
218.000	
219.000	
220.000	
221.000	
222.000	
223.000	
224.000	
225.000	
226.000	
227.000	
228.000	
229.000	
230.000	
231.000	
232.000	
233.000	
234.000	
235.000	
236.000	
237.000	
238.000	
239.000	
240.000	
241.000	
242.000	
243.000	
244.000	
245.000	
246.000	
247.000	
248.000	
249.000	
250.000	
251.000	
252.000	
253.000	
254.000	
255.000	
256.000	
257.000	
258.000	
259.000	
260.000	
261.000	
262.000	
263.000	
264.000	
265.000	
266.000	
267.000	
268.000	
269.000	
270.000	
271.000	
272.000	
273.000	
274.000	
275.000	
276.000	
277.000	
278.000	
279.000	
280.000	
281.000	
282.000	
283.000	
284.000	
285.000	
286.000	
287.000	
288.000	
289.000	
290.000	
291.000	
292.000	
293.000	
294.000	
295.000	
296.000	
297.000	
298.000	
299.000	
300.000	
301.000	
302.000	
303.000	
304.000	
305.000	
306.000	
307.000	
308.000	
309.000	
310.000	
311.000	
312.000	
313.000	
314.000	
315.000	
316.000	
317.000	
318.000	
319.000	
320.000	
321.000	
322.000	
323.000	
324.000	
325.000	
326.000	
327.000	
328.000	
329.000	
330.000	
331.000	
332.000	
333.000	
334.000	
335.000	
336.000	
337.000	
338.000	
339.000	
340.000	
341.000	
342.000	
343.000	
344.000	
345.000	
346.000	
347.000	
348.000	
349.000	
350.000	
351.000	
352.000	
353.000	
354.000	
355.000	
356.000	
357.000	
358.000	
359.000	
360.000	
361.000	
362.000	
363.000	
364.000	
365.000	
366.000	
367.000	
368.000	
369.000	
370.000	
371.000	
372.000	
373.000	
374.000	
375.000	
376.000	
377.000	
378.000	
379.000	
380.000	
381.000	
382.000	
383.000	
384.000	
385.000	
386.000	
387.000	
388.000	
389.000	
390.000	
391.000	
392.000	
393.000	
394.000	
395.000	
396.000	
397.000	
398.000	
399.000	
400.000	
401.000	
402.000	
403.000	
404.000	
405.000	
406.000	
407.000	
408.000	
409.000	
410.000	
411.000	
412.000	
413.000	
414.000	
415.000	
416.000	
417.000	
418.000	
419.000	
420.000	
421.000	
422.000	
423.000	
424.000	
425.000	
426.000	
427.000	
428.000	
429.000	
430.000	
431.000	
432.000	
433.000	
434.000	
435.000	
436.000	
437.000	
438.000	
439.000	
440.000	
441.000	
442.000	
443.000	
444.000	
445.000	
446.000	
447.000	
448.000	
449.000	
450.000	
451.000	
452.000	
453.000	
454.000	
455.000	
456.000	
457.000	
458.000	
459.000	
460.000	
461.000	
462.000	
463.000	
464.000	
465.000	
466.000	
467.000	
468.000	
469.000	
470.000	
471.000	
472.000	
473.000	
474.000	
475.000	
476.000	
477.000	
478.000	
479.000	
480.000	
481.000	
482.000	
483.000	
484.000	
485.000	
486.000	
487.000	
488.000	
489.000	
490.000	
491.000	
492.000	
493.000	
494.000	
495.000	
496.000	
497.000	
498.000	
499.000	
500.000	
501.000	
502.000	
503.000	
504.000	
505.000	
506.000	
507.000	
508.000	
509.000	
510.000	
511.000	
512.000	
513.000	
514.000	
515.000	
516.000	
517.000	
518.000	
519.000	
520.000	
521.000	
522.000	
523.000	
524.000	
525.000	
526.000	
527.000	
528.000	
529.000	
530.000	
531.000	
532.000	
533.000	
534.000	
535.000	
536.000	
537.000	
538.000	
539.000	
540.000	
541.000	
542.000	
543.000	
544.000	
545.000	
546.000	
547.000	
548.000	
549.000	
550.000	
551.000	
552.000	
553.000	
554.000	
555.000	
556.000	
557.000	
558.000	
559.000	
560.000	
561.000	
562.000	
563.000	
564.000	
565.000	
566.000	
567.000	
568.000	
569.000	
570.000	
571.000	
572.000	
573.000	
574.000	
575.000	
576.000	
577.000	
578.000	
579.000	
580.000	
581.000	
582.000	
583.000	
584.000	
585.000	
586.000	
587.000	
588.000	
589.000	
590.000	
591.000	
592.000	
593.000	
594.000	
595.000	
596.000	
597.000	
598.000	
599.000	
600.000	
601.000	
602.000	
603.000	
604.000	
605.000	
606.000	
607.000	
608.000	
609.000	
610.000	
611.000	
612.000	
613.000	
614.000	
615.000	
616.000	
617.000	
618.000	
619.	





# Executive Capital Improvement Plan 2023

Project Name --->> Facilities -COG Boiler Replacement								
ANTICIPATED PROJECT COSTS AND SOURCES OF FUNDS:								
	Prior years	2023	2024	2025	2026	2027	Beyond	Total
<b>PROJECT COST'S</b>								
Planning, Design, Engineering		10,000						10,000
Land Purchase								-
Construction								-
Equipment			150,000					150,000
Other								-
TOTAL	-	10,000	150,000	-	-	-	-	160,000
<b>PROJECT FUNDS</b>								
County Funding		10,000	150,000					160,000
Outside funding								-
Operating Tax Levy								-
Previous bonding								-
TOTAL	-	10,000	150,000	-	-	-	-	160,000

## Project Description:

This project is to replace the two existing hot water boilers in the JP Coughlin Center. These boilers were installed in 1998 and have reached 24 years of age. The interior firebox structure is deteriorating to the point the boilers need to be replaced. The boilers are approximately 75% efficient. New boilers would get the efficiency up to 90+%. . Annual repair costs are beginning to increase. Several of the components are obsolete requiring modern components to be retrofitted and modified to work with the boiler. Projected fuel savings are estimated at \$7500 per year.

## Relationship to Other Projects:

This project is not related to any other project.

## Justification & Alternatives Considered

There are two alternatives. The first is to do nothing and continue to operate the existing boilers. This will lead to continued higher energy costs, less efficient operation and the potential that repairs will be more expensive as the older technology is more difficult to find. The other alternative is to replace the existing boilers with more energy efficient boilers.





# Executive Capital Improvement Plan 2023

Project Name --->> Facilities -Courthouse Fall Protection								
ANTICIPATED PROJECT COSTS AND SOURCES OF FUNDS:								
	Prior years	2023	2024	2025	2026	2027	Beyond	Total
<b>PROJECT COST'S</b>								
Planning, Design, Engineering								-
Land Purchase								-
Construction		125,000						125,000
Equipment								-
Other								-
<b>TOTAL</b>	-	125,000	-	-	-	-	-	125,000
<b>PROJECT FUNDS</b>								
County Funding		125,000						125,000
Outside funding								-
Operating Tax Levy								-
Previous bonding								-
<b>TOTAL</b>	-	125,000	-	-	-	-	-	125,000

## **Project Description:**

This project is to install OSHA required fall protection on the roof of the Courthouse. Currently there are no safety provisions for working on the roof. At least annually staff are needed to inspect the building masonry and to clean the roof drains. The OSHA Fall Protection Standard was updated in 2015. It now requires protection whenever a person is within 6 feet of the roof edge. It also requires that any attachment point has to be engineered and tested to OSHA requirements. The Courthouse has no attachment points currently installed.

## **Relationship to Other Projects:**

This project is not associated with any other project or plan.

## **Justification & Alternatives Considered**

There really is no alternative to this required work. The OSHA standard applies to both employees and contractors. For any person to repair the roof drains or to inspect building structure within 6 feet of the roof edge, there needs to be equipment with fall protection.



# Executive Capital Improvement Plan 2023

Project Name ----> Facilities - Masonry Maintenance Program								
ANTICIPATED PROJECT COSTS AND SOURCES OF FUNDS:								
	Prior years	2023	2024	2025	2026	2027	Beyond	Total
<b>PROJECT COST'S</b>								
Planning, Design, Engineering		12,000	12,000	10,000	8,000	10,000		52,000
Land Purchase								-
Construction		150,000	150,000	150,000	125,000	150,000		725,000
Equipment								-
Other								-
<b>TOTAL</b>	-	162,000	162,000	160,000	133,000	160,000	-	777,000
<b>PROJECT FUNDS</b>								
County Funding		150,000	150,000	150,000	125,000	150,000		725,000
Outside funding								-
Operating Tax Levy		12,000	12,000	10,000	8,000	10,000		52,000
Previous bonding								-
<b>TOTAL</b>	-	162,000	162,000	160,000	133,000	160,000	-	777,000

## Project Description:

This project is to maintain and repair the masonry surfaces of various County Facilities. Each building will be surveyed on a regular basis to identify potential masonry problems before they actually occur. Remedial action will be taken to prevent a building envelop failure and more costly repairs or replacement. The goal of this program is to maximize the life of the masonry surfaces covering the facilities.

Schedule of Masonry Repairs						
	2023	2024	2025	2026	2027	Beyond
<b>PROJECT COSTS</b>						
Highway Shop		150,000				
Otter Street Building	150,000					
Neenah Building					150,000	150,000
Airport Tower			150,000			
Oshkosh Human Services				125,000		
Coughlin						100,000
Jail						125,000
Maintenance Facility						100,000
<b>TOTAL</b>	150,000	150,000	150,000	125,000	150,000	475,000
Jail expansion joints last repaired in 2014 - \$224,850 (Statz), \$13500(Kontext)						
Maintenance Facility tuckpointing last repaired in 2012						
King Building tuckpointing was addressed in 2020						
Courthouse is ongoing 2021-2022						

## Relationship to Other Projects:

This project works in conjunction with the Comprehensive Needs Study and all the other projects for each facility. If a facility is scheduled for major renovation, masonry repairs will become a part of that project to minimize disruption to the facility occupants and consolidate work done to the facility. If a facility is scheduled for disposal, only the basic maintenance of the masonry will be accomplished, avoiding unnecessary costs.


## Justification & Alternatives Considered

There are two alternatives to this program. The first is to do minimal planning. This will continue the current practice of having masonry joints fail without warning and causing other collateral damage due to water or weather intrusion. Emergency repairs are costly and are usually performed under less than ideal conditions. There usually is no funding for emergency repairs. The repairs are very disruptive to the facility occupants. The collateral damage due to water leakage or weather intrusion can be very costly due to electronic equipment that may be damaged, employee or visitor injuries. The second alternative is to have a proactive masonry maintenance program. This program will identify potential masonry problems before they occur. Repairs can be planned and funded through the budget process. Occupants are aware of pending repairs and plans can be established to minimize disruption to the daily activities. Projects can be competitively bid early in the season to get the best price.



# Executive Capital Improvement Plan 2023

Project Name: Facilities – Masonry Maintenance Program - Highway Office, Shop and Facade







## COUNTY ADMINISTRATION BUILDINGS MASONRY TUCKPOINTING

### PROJECT LOCATION



**SHEET INDEX**

G100	TITLE SHEET
A100	ELEVATIONS
A101	ELEVATIONS
A102	ELEVATIONS
A103	CALLOUTS
A104	CALLOUTS

CBS SQUARED, INC.  
770 TECHNOLOGY WAY  
CHIPPEWA FALLS, WI 54729  
(715) 861-5226  
CONTACTS: BOB SWORSKI, AIA/NCARB, ARCHITECT  
CHAD OSTER, ASSOC. AIA, PROJECT LEADER




GENERAL NOTES:

- [illegible]

A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y	Z					
TITLE SHEET	PROJECT #	DATE OF BIRTH	DATE OF DEATH	DATE OF BIRTH	DATE OF DEATH	DATE OF BIRTH	DATE OF DEATH	DATE OF BIRTH	DATE OF DEATH	DATE OF BIRTH	DATE OF DEATH	DATE OF BIRTH	DATE OF DEATH	DATE OF BIRTH	DATE OF DEATH	DATE OF BIRTH	DATE OF DEATH	DATE OF BIRTH	DATE OF DEATH	DATE OF BIRTH	DATE OF DEATH	DATE OF BIRTH	DATE OF DEATH	DATE OF BIRTH	DATE OF DEATH	DATE OF BIRTH	DATE OF DEATH			
COUNTY ADMIN.	BUILDINGS MASONRY	TUCK POINTING	COUNTY ADMIN.	BUILDINGS MASONRY	TUCK POINTING	COUNTY ADMIN.	BUILDINGS MASONRY	TUCK POINTING	COUNTY ADMIN.	BUILDINGS MASONRY	TUCK POINTING	COUNTY ADMIN.	BUILDINGS MASONRY	TUCK POINTING	COUNTY ADMIN.	BUILDINGS MASONRY	TUCK POINTING	COUNTY ADMIN.	BUILDINGS MASONRY	TUCK POINTING	COUNTY ADMIN.	BUILDINGS MASONRY	TUCK POINTING	COUNTY ADMIN.	BUILDINGS MASONRY	TUCK POINTING	COUNTY ADMIN.	BUILDINGS MASONRY	TUCK POINTING	
ENGINEERS - SURVEYORS ATTACHED	770 Technology Way	Chippewa Falls, WI 54720	Phone: 715.811.5226	770 Technology Way	Chippewa Falls, WI 54720	Phone: 715.811.5226	770 Technology Way	Chippewa Falls, WI 54720	Phone: 715.811.5226	770 Technology Way	Chippewa Falls, WI 54720	Phone: 715.811.5226	770 Technology Way	Chippewa Falls, WI 54720	Phone: 715.811.5226	770 Technology Way	Chippewa Falls, WI 54720	Phone: 715.811.5226	770 Technology Way	Chippewa Falls, WI 54720	Phone: 715.811.5226	770 Technology Way	Chippewa Falls, WI 54720	Phone: 715.811.5226	770 Technology Way	Chippewa Falls, WI 54720	Phone: 715.811.5226	770 Technology Way	Chippewa Falls, WI 54720	Phone: 715.811.5226
COUNTY ADMIN.	BUILDINGS MASONRY	TUCK POINTING	COUNTY ADMIN.	BUILDINGS MASONRY	TUCK POINTING	COUNTY ADMIN.	BUILDINGS MASONRY	TUCK POINTING	COUNTY ADMIN.	BUILDINGS MASONRY	TUCK POINTING	COUNTY ADMIN.	BUILDINGS MASONRY	TUCK POINTING	COUNTY ADMIN.	BUILDINGS MASONRY	TUCK POINTING	COUNTY ADMIN.	BUILDINGS MASONRY											



1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40	41	42	43	44	45	46	47	48	49	50	51	52	53	54	55	56	57	58	59	60	61	62	63	64	65	66	67	68	69	70	71	72	73	74	75	76	77	78	79	80	81	82	83	84	85	86	87	88	89	90	91	92	93	94	95	96	97	98	99	100
1	2	3	4	5	6	7	8	9	10	11	12	13</																																																																																							


[illegible]

COUNTY ADMIN.  
 BUILDINGS MASONRY  
 179 Beckoning Way  
 Capehart, Pa. 16129  
 814-337-7878  
 FAX 814-337-7880  
 179 Beckoning Way  
 Capehart, Pa. 16129  
 814-337-7878  
 FAX 814-337-7880



# Executive Capital Improvement Plan 2023

## Project Name: Facilities - Masonry Maintenance Program - Otter Street







# Executive Capital Improvement Plan 2023

Project Name --->> Facilities - NHS Boiler Replacement								
ANTICIPATED PROJECT COSTS AND SOURCES OF FUNDS:								
	Prior years	2023	2024	2025	2026	2027	Beyond	Total
<b>PROJECT COST'S</b>								
Planning, Design, Engineering		10,000						10,000
Land Purchase								-
Construction								-
Equipment			150,000					150,000
Other								-
TOTAL	-	10,000	150,000	-	-	-	-	160,000
<b>PROJECT FUNDS</b>								
County Funding		10,000	150,000					160,000
Outside funding								-
Operating Tax Levy								-
Previous bonding								-
TOTAL	-	10,000	150,000	-	-	-	-	160,000

## **Project Description:**

This project is to replace the two existing hot water boilers in the Neenah Human Services Building. These boilers were installed in 1994 and have reached 25+ years of age. The interior firebox structure is deteriorating to the point the boilers need to be replaced. The boilers are approximately 75% efficient. New boilers would get the efficiency up to 90+%. . Annual repair costs are beginning to increase. Several of the components are obsolete requiring modern components to be retrofitted and modified to work with the boiler. Projected fuel savings are estimated at \$7500 per year.

## **Relationship to Other Projects:**

This project is not associated with any other project or plan.

## **Justification & Alternatives Considered**

There are two alternatives. The first is to do nothing and continue to operate the existing boilers. This will lead to continued higher energy costs, less efficient operation and the potential that repairs will be more expensive as the older technology is more difficult to find. The other alternative is to replace the existing boilers with more energy efficient boilers.



# Executive Capital Improvement Plan 2023

Project Name --->> Facilities - Park View Fire Alarm Replacement								
ANTICIPATED PROJECT COSTS AND SOURCES OF FUNDS:								
	Prior years	2023	2024	2025	2026	2027	Beyond	Total
<b>PROJECT COST'S</b>								
Planning, Design, Engineering		10,000						10,000
Land Purchase								-
Construction								-
Equipment		103,640						103,640
Other								-
TOTAL	-	113,640	-	-	-	-	-	113,640
<b>PROJECT FUNDS</b>								
County Funding		103,640						103,640
Outside funding								-
Operating Tax Levy		10,000						10,000
Previous bonding								-
TOTAL	-	113,640	-	-	-	-	-	113,640

## **Project Description:**

This project is to replace the proprietary fire alarm system with a new replacement non-proprietary fire alarm system. The existing fire alarm was originally installed when the building was built in 2008. It is experiencing numerous programming and computer glitches that require multiple visits from the sole contractor that can service the system and significant time requirements from Park View staff. While resident safety has not been compromised, their quality of life has been affected. Because the system is proprietary, competitive pricing for replacement parts and service providers is virtually non-existent. A non-proprietary system will allow competitive pricing for parts and service and also the opportunity to change service providers due to poor response and service.

## **Relationship to Other Projects:**

This project is not associated with any other project or plan.

## **Justification & Alternatives Considered**

There are two alternatives. The first is to do nothing and continue to operate the existing fire alarm and incur the increasing costs for maintenance. The other is to replace the fire alarm with a non-proprietary fire alarm.



# Executive Capital Improvement Plan 2023

Project Name ---> Facilities - Roof Replacement Program								
ANTICIPATED PROJECT COSTS AND SOURCES OF FUNDS:								
	Prior years	2023	2024	2025	2026	2027	Beyond	Total
<b>PROJECT COST'S</b>								
Planning, Design, Engineering	15,440	18,561	22,635	16,063	12,565	10,880		96,144
Land Purchase								-
Construction	133,650	257,063	308,491	222,464	174,027	150,691		1,246,386
Equipment								-
Other								-
<b>TOTAL</b>	<b>149,090</b>	<b>275,624</b>	<b>331,126</b>	<b>238,527</b>	<b>186,592</b>	<b>161,571</b>	<b>-</b>	<b>1,342,530</b>
<b>PROJECT FUNDS</b>								
County Funding	133,650	275,624	331,126	238,527	186,592	161,571		1,327,090
Outside funding								-
Operating Tax Levy	15,440							15,440
Previous bonding								-
<b>TOTAL</b>	<b>149,090</b>	<b>275,624</b>	<b>331,126</b>	<b>238,527</b>	<b>186,592</b>	<b>161,571</b>	<b>-</b>	<b>1,342,530</b>

## **Project Description:**

This project is to replace the roof surfaces of various County Facilities. Each building will be surveyed on a regular basis to identify potential roof problems before they actually occur. Remedial action will be taken to prevent a building envelop failure and more costly repairs or replacement. The goal of this program is to maximize the life of the roofs surfaces covering the facilities.

## **Relationship to Other Projects:**

This project works in conjunction with the Comprehensive Needs Study and all the other projects for each facility. If a facility is scheduled for major renovation, roof replacement will become a part of the project to minimize disruption to the facility occupants and consolidate work done to a facility. If a facility is scheduled for disposal, only the basic maintenance of the roof will be accomplished, avoiding unnecessary costs.

## **Justification & Alternatives Considered**

There are two alternatives to this program. The first is to do minimal planning. This will continue the current practice of having roofs fail without warning and causing other collateral damage due to water or weather intrusion. Emergency repairs are costly and are usually performed under less than ideal conditions. There usually is no funding for emergency repairs. The repairs are very disruptive to the facility occupants. The collateral damage due to water leakage or weather intrusion can be very costly due to electronic equipment that may be damaged, employee or visitor injuries. There are two alternatives to this program. The first is to do minimal planning. This will continue the current practice of having roofs fail without warning and causing other collateral damage due to water or weather intrusion. Emergency repairs are costly and are usually performed under less than ideal conditions. There usually is no funding for emergency repairs. The repairs are very disruptive to the facility occupants. The collateral damage due to water leakage or weather intrusion can be very costly due to electronic equipment that may be damaged, employee or visitor injuries.



# Executive Capital Improvement Plan 2023

## Project Name: Facilities - Roof Replacement Program

Roof Replacement Estimate				
Building	Square Foot of Roof	Phase	Cost/SF	Subtotal
Neenah Human Services	20500	Design	8%	\$ 18,561
		Removal/Install	Online Est	\$ 232,007
		Contingency	10%	\$ 25,057
Total				\$ 275,624
Expo Center (Metal Roof)	64434	Design	8%	\$ 80,445
		Removal/Install	15%	\$ 1,005,557
		Contingency	10%	\$ 108,600
Total				\$ 1,194,602
Otter Street Bldg	25000	Design	8%	\$ 22,635
		Removal/Install	Online Est	\$ 282,935
		Contingency	10%	\$ 30,557
				\$ 336,126
Waugoo St Bldg	17000	Design	8%	\$ 13,518
		Removal/Install	Online Est	\$ 168,973
		Contingency	10%	\$ 18,249
				\$ 200,740
State St Bldg	3200	Design	8%	\$ 2,545
		Removal/Install	Online Est	\$ 31,807
		Contingency	10%	\$ 3,435
				\$ 37,787
Airport Fire Station	7500	Design	8%	\$ 5,549
		Removal/Install	Online Est	\$ 69,361
		Contingency	10%	\$ 7,491
				\$ 82,401
Park View	70000	Design	8%	\$ 33,953
		Removal/Install	Online Est	\$ 424,416
		Contingency	10%	\$ 45,837
Shingle Peaks				\$ 504,206
	70000	Design	8%	\$ 50,774
		Removal/Install	Online Est	\$ 634,679
		Contingency	10%	\$ 68,545
Flat Roof				\$ 753,999
Airport Tower	9000	Design	8%	\$ 7,016
		Removal/Install	Online Est	\$ 87,703
		Contingency	10%	\$ 9,472
				\$ 104,191
Jail	175000	Design	8%	\$ 136,426
		Removal/Install	Online Est	\$ 1,705,329
		Contingency	10%	\$ 184,176
				\$ 2,025,931
Jail Evidence Garage	15000	Design	8%	\$ 10,880
		Removal/Install	Online Est	\$ 136,003
		Contingency	10%	\$ 14,688
				\$ 161,571
Fairview	1200	Design	8%	\$ 822
		Removal/Install	Online Est	\$ 10,270
		Contingency	10%	\$ 1,109
				\$ 12,201
Oshkosh Human Services	25000	Design	8%	\$ 19,489
		Removal/Install	Online Est	\$ 243,618
		Contingency	10%	\$ 26,311
				\$ 289,418

Roof Replacement Schedule						
	2023	2024	2025	2026	2027	Beyond
Coughlin Building Roof						Completed 2019
King Building						Completed 2021
Neenah Human Services Building	275,624					
Otter Street Bldg		336,126				
Second Chance			200,740			
State Street Building			37,787			
Airport Fire Station				82,401		
Park View						1,209,347 FY 2028
Airport Tower				104,191		
Jail						1,947,261 FY 2033
Evidence Garage					161,571	
Oshkosh Human Services Building						278,180 FY 2030
Total	275,624	336,126	238,527	186,592	161,571	3,434,788





# Executive Capital Improvement Plan 2023

Project Name: Facilities - Roof Replacement Program







# Executive Capital Improvement Plan 2023

Project Name --->> Highway - CTH F (Omro to CTH D)								
ANTICIPATED PROJECT COSTS AND SOURCES OF FUNDS:								
	Prior years	2023	2024	2025	2026	2027	Beyond	Total
<b>PROJECT COST'S</b>								
Planning, Design, Engineering								-
Land Purchase								-
Construction		1,626,818						1,626,818
Equipment								-
Other								-
TOTAL	-	1,626,818	-	-	-	-	-	1,626,818
<b>PROJECT FUNDS</b>								
County Funding		1,626,818						1,626,818
Outside funding								-
Operating Tax Levy								-
Previous bonding								-
TOTAL	-	1,626,818	-	-	-	-	-	1,626,818

## **Project Description:**

This 4.0 mile segment will be profile milled and have an asphalt overlay installed to improve the paved surface along with minor drainage improvements.

## **Relationship to Other Projects:**

Pavement improvements on roadways that cannot be economically maintained are essential to provide pavement conditions that are safe and promote commerce within the county.

## **Justification & Alternatives Considered**


The existing pavement is in poor condition and is beyond the point at which preventative maintenance would not be a cost effective alternative.



# Executive Capital Improvement Plan 2023

Project Name: Highway – CTH F (Omro to CTH D)

ArcGIS Web Map



10/27/2022, 2:01:12 PM

Local Road    State Road    Interstate  
County Road    US Highway    WinnebagoCo2020  
Red: Band\_1    Green: Band\_2    Blue: Band\_3

1:83,175  
0 0.5 1 2 mi  
0 1 2 4 km  
Winnebago County GIS, Winnebago County

Winnebago County GIS | NRCS Spring, 1976 | Imagery Date: March, 1994 | Imagery Date: March, 1997 | Imagery Date: March, 2000 | Imagery Date: April, 2003 | Imagery Date: April, 2005 | Imagery Date: April, 2009 | USDA-FSA Aerial Photography Field Office: ArcGIS Web AppBuilder



# Executive Capital Improvement Plan 2023

Project Name --->> Highway - CTH JJ (CTH CB to South 76)								
ANTICIPATED PROJECT COSTS AND SOURCES OF FUNDS:								
	Prior years	2023	2024	2025	2026	2027	Beyond	Total
PROJECT COSTS								
Planning, Design, Engineering								-
Land Purchase								-
Construction		929,600						929,600
Equipment								-
Other								-
TOTAL	-	929,600	-	-	-	-	-	929,600
PROJECT FUNDS								
County Funding		929,600						929,600
Outside funding								-
Operating Tax Levy								-
Previous bonding								-
TOTAL	-	929,600	-	-	-	-	-	929,600

## **Project Description:**

This 2.3 mile segment of roadway includes milling existing asphalt pavement, installing a new asphalt surface, minor tree trimming and minor drainage improvements.

## **Relationship to Other Projects:**

Pavement improvements on roadways that cannot be economically maintained are essential to provide pavement conditions that are safe and promote commerce within the county. With recently resurfaced CTH-CB, newly constructed roundabout at CTH-CB & CTH-JJ and a new roundabout at STH-76 & CTH-JJ, this proposed resurfacing project will improve travel within this corridor.

## **Justification & Alternatives Considered**

The existing pavement which was last overlaid in 2005 is in poor condition and beyond the point at which preventative maintenance would not be a cost effective alternative.






# Executive Capital Improvement Plan 2023

Project Name: Highway - CTH JJ (CTH CB to South 76)

ArcGIS Web Map





# Executive Capital Improvement Plan 2023

Project Name ---> Highway - CTH P (Midway Road to South 47)								
ANTICIPATED PROJECT COSTS AND SOURCES OF FUNDS:								
	Prior years	2023	2024	2025	2026	2027	Beyond	Total
<b>PROJECT COST'S</b>								
Planning, Design, Engineering	780,000							780,000
Land Purchase		150,000						150,000
Construction				6,500,000				6,500,000
Equipment								-
Other								-
<b>TOTAL</b>	<b>780,000</b>	<b>150,000</b>	<b>-</b>	<b>6,500,000</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>7,430,000</b>
<b>PROJECT FUNDS</b>								
County Funding	98,280	150,000		1,229,700				1,477,980
Outside funding	681,720			5,270,300				5,952,020
Operating Tax Levy								-
Previous bonding								-
<b>TOTAL</b>	<b>780,000</b>	<b>150,000</b>	<b>-</b>	<b>6,500,000</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>7,430,000</b>

## **Project Description:**

The segment between STH "47" and Midway Road involves designing and constructing the roadway to current standards. The existing roadway is a two lane rural cross section with gravel shoulders and ditches within an urbanized area. The pavement is failing and drainage is a problematic with frequent flooding during heavy rainfall events and spring runoff. The roadway will be designed and constructed to a two lane urban cross section with a two way left turn lane to safely accommodate turning movements. The roadway is also anticipated to incorporate bicycles and pedestrians.

## **Relationship to Other Projects:**

This project ties into the future plans to connect into a new stormwater detention pond located at Midway Rd and STH "441". The Village, City, and County entered into an agreement with WisDOT to reduce suspended solids and claim storm water credits which will allow the construction of CTH "P" to meet MS4 requirements.

## **Justification & Alternatives Considered**

CTH "P" is in need of reconstruction, the current two lane rural cross section between STH "47" and Midway Road does not function effectively, numerous driveways to multiple businesses are causing issues with drainage. The pavement is failing and is inadequate to handle the traffic that is currently using the roadway. There are no bicycle or pedestrian accommodations which are needed due to the mix of commercial and residential development surrounding the roadway corridor.






# Executive Capital Improvement Plan 2023

Project Name: Highway - CTH P (Midway Road to South 47)

ArcGIS Web Map



10/19/2021, 6:52:46 AM

Road ROW area

Road ROW

Street Centerline

Railroads


Tax Parcels

Air Photo 2020

Red: Band\_1

Green: Band\_2

Blue: Band\_3



Winnebago County GIS, Winnebago County

ArcGIS Web AppBuilder

Winnebago County GIS | Imagery Data: March 2015 | Winnebago County



# Executive Capital Improvement Plan 2023

Project Name ---> Highway - Building Upgrades								
ANTICIPATED PROJECT COSTS AND SOURCES OF FUNDS:								
	Prior years	2023	2024	2025	2026	2027	Beyond	Total
<b>PROJECT COST'S</b>								
Planning, Design, Engineering	320,000							320,000
Land Purchase								-
Construction		2,500,000	2,500,000					5,000,000
Equipment								-
Other								-
<b>TOTAL</b>	<b>320,000</b>	<b>2,500,000</b>	<b>2,500,000</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>5,320,000</b>
<b>PROJECT FUNDS</b>								
County Funding	320,000	2,500,000	2,500,000					5,320,000
Outside funding								-
Operating Tax Levy								-
Previous bonding								-
<b>TOTAL</b>	<b>320,000</b>	<b>2,500,000</b>	<b>2,500,000</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>5,320,000</b>

## Relationship to Other Projects:

This project is not associated with any other project or plan.

## Justification & Alternatives Considered

This project is a necessary repair for both the health and safety of the employees and to prevent unnecessary damage to the building structure. If left unchecked the interior finishes will continue to be damaged and mold will grow unchecked. The free movement of air from the outside will continue to tax the building HVAC system and hasten its replacement due to a shortened life. The modernization of the building will allow the department to store, maintain and operate the equipment more effectively. The additional office space will allow public meetings to be held and accommodate the attendees. There really are only two alternatives. The first is to leave the building as it is and deal with the problems on an ongoing basis. The other is to make these repairs and modernization.

## Project Description:

This project is to address two problems at the Highway Department Office and Shop. The first is an ongoing issue with moisture infiltration into the Highway Department Office. Over the years moisture has entered the building through porous exterior walls. There are no moisture or vapor barriers on the exterior walls. The walls have minimal insulation. Additionally there is free passage of exterior air through the soffits into the interior of the building. This allows whatever humidity that is outside to move into the interior. If the building is being air conditioned in the summer and there is high humidity outside, it enters the building and then condenses onto the interior building structure. This damages the interior of the building and it makes the air conditioning system work harder to cool the interior. Because of the years of this occurring the interior of the building has been damaged by the moisture and requires replacement. This project will waterproof the exterior of the building, seal the gaps between the walls and soffits and replace the interior finishes of the office area, to include the drywall, carpet and ceiling tiles. The second issue is the Highway Department has changed over the 30 years that this building has been used. The work force is changing being more diverse requiring enlarged locker room space for female staff. The equipment has gotten more diverse also, being bigger and more complex. This requires more space to park and maintain the equipment to maximize its life. In this project a larger more accommodating vehicle wash bay is created. Larger parking space is provided for the tow plow equipment. Additional office space and meeting space is provided to accommodate public meeting. Road salt has become a challenging to obtain. This project would increase the capacity of the existing salt shed.





# Executive Capital Improvement Plan 2023

## Project Name: Highway – Building Upgrades

Winnebago County Public Works Building BER Assessment

Page 2 of 3

San Prairie - Madison Office  
242 East Main Street, Suite #201  
San Prairie, WI 53590  
T: 608.825.0094  
F: 608.251.7515  
F: 866.926.9351



Wausau Office  
4404 Rib Mountain Drive #244  
Wausau, WI 54401  
T: 715.803.2736  
F: 866.926.9351

October 5, 2021

Mr. Michael Elder  
Director of Facilities, Maintenance & Planning  
Winnebago County - Maintenance Facility  
1221 Knapp Street  
Oshkosh, WI 54902

RE: Winnebago County Public Works Building BER Assessment

Dear Mike,

Below you will find our Observations and Recommendations as it relates to the performance of the exterior walls and windows at the public works garage.

### Observations

The existing building consists of administrative and garage areas. The Administration/Office area section is a small portion of the overall building footprint. The Administration / Office area is ventilated, heated and cooled for year-round occupancy. The garage is ventilated and heated customarily for this occupancy.



Administration /  
Offices

Garage

**Exterior Walls:** The Administration/Office exterior wall assembly consists of a single wythe, split-face concrete masonry unit structure. It is finished on the inside with 1 ½" of rigid insulation and gypsum wall board. The Garage is limited to the split face block structure painted on the inside. We are uncertain if the cores of the structure have been filled with insulation to increase the thermal performance of the exterior wall.

**Fenestration:** The Administration / Office area include windows (punched openings) construction of simplistic storefront framing. The Garage is limited to large overhead doors, man doors, a few windows and various mechanical penetrations.

**Concerns:** It is understood and observed that the Administration / Office area experiences poor air quality due to high moisture levels. Deterioration of finishes at window openings is common. There is also a concern that space above the ceilings is continuous between the interior and exterior at the exterior soffits.

**Discussion:** This type of construction (single wythe masonry) has a history of poor performance when not detailed properly. The absence of through wall flashing assemblies at punched openings, horizontal bond beams, sills, and wall base is detrimental to the overall ability of the wall to manage moisture. Additionally, an ill placed (outboard) window assembly within the wall will provide ample opportunity for moisture migration.

**Assessment:** The existing conditions offer both scenarios; absent through-wall flashing and outboard placed windows. For the Administration / Offices area, the concerns can be largely attributed to these shortcomings. To further complicate matters, we suspect that an inboard vapor barrier (warm side of the insulation) is not present. Additionally, discontinuity of the thermal envelope (open soffits) will also contribute to the adverse conditions.

Although the garage lacks the same attention to details, we believe that the lack of gypsum board finishes, the volume of the space, and the make-up air (usually 100% for this occupancy) tends to keep any unwanted moisture migration dry. We did observe that some of the larger opening lintels are causing distress in adjoining masonry. This is not uncommon due to anticipated deflection of the steel under load.

### Recommendations:

Administration / Office:

1. Given the complete lack of through wall flashing systems, the application of a breathable masonry coating and completion of sealant replacement over the entire façade is recommended. This will mitigate water infiltration into the porous surface of the masonry.
2. Replace the existing windows, moving them inboard. This will help align the window assembly with the thermal plane of the exterior wall (inside face) and away for the drainage plane (outside face).
3. Replace interior finishes including insulation, furring, and gypsum board, offering thermal improvements and implementation of a vapor retarder. This will impact ceilings, consequently, any discontinuity in the exterior thermal envelope (ie soffits) can be remedied.


**Garage:** One could argue that the exterior walls can be essentially left alone to maintenance of sealants and painting of lintels in lieu of comprehensive coating project. However, some localized masonry repairs could be pursued at lintels. Alternatively, the



# Executive Capital Improvement Plan 2023

Project Name: Highway – Building Upgrades

## Preliminary Sketch of changes to the building and area





# Executive Capital Improvement Plan 2023

Project Name ---> Highway - CTH II (US 45 - N CTY Line)								
ANTICIPATED PROJECT COSTS AND SOURCES OF FUNDS:								
	Prior years	2023	2024	2025	2026	2027	Beyond	Total
<b>PROJECT COST'S</b>								
Planning, Design, Engineering								-
Land Purchase								-
Construction		2,337,006						2,337,006
Equipment								-
Other								-
TOTAL	-	2,337,006	-	-	-	-	-	2,337,006
<b>PROJECT FUNDS</b>								
County Funding		1,886,365						1,886,365
Outside funding		450,641						450,641
Operating Tax Levy								-
Previous bonding								-
TOTAL	-	2,337,006	-	-	-	-	-	2,337,006

## **Project Description:**

This 6.6 mile segment will be profile milled and have an asphalt overly installed to improve the paved surface which is deteriorating and in need of improvement.

## **Relationship to Other Projects:**

This project is part of the long term plans to maintain and replace roads and bridges that are part of the county roadway system. The objective is to keep the annual spending relatively stable while maintaining good driving conditions on all county roads over time.

## **Justification & Alternatives Considered**

The existing asphalt surface will continue to degrade where routine maintenance will not be adequate to maintain the surface, installing an asphalt overlay will provide a useful life for 10 - 15. Pulverizing the existing asphalt was considered however given the projected pavement condition and future plans to reconstruct the roadway, an overlay is an appropriate alternative and less costly.





# Executive Capital Improvement Plan 2023

Project Name --->> Highway - CTH II (US 45 - N CTY Line)								
ANTICIPATED PROJECT COSTS AND SOURCES OF FUNDS:								
	Prior years	2023	2024	2025	2026	2027	Beyond	Total
<b>PROJECT COST'S</b>								
Planning, Design, Engineering								-
Land Purchase								-
Construction		1,442,000						1,442,000
Equipment								-
Other								-
<b>TOTAL</b>	-	1,442,000	-	-	-	-	-	1,442,000
<b>PROJECT FUNDS</b>								
County Funding		991,369						991,369
Outside funding		450,641						450,641
Operating Tax Levy								-
Previous bonding								-
<b>TOTAL</b>	-	1,442,010	-	-	-	-	-	1,442,010

## **Project Description:**

This 9.7 mile segment will be profile milled and have an asphalt overly installed to improve the paved surface which is deteriorating and in need of improvement.

## **Relationship to Other Projects:**

This project is part of the long term plans to maintain and replace roads and bridges that are part of the county roadway system. The objective is to keep the annual spending relatively stable while maintaining good driving conditions on all county roads over time.


## **Justification & Alternatives Considered**

The existing asphalt surface will continue to degrade where routine maintenance will not be adequate to maintain the surface, installing an asphalt overlay will provide a useful life for 15 - 20. Pulverizing the existing asphalt was considered however given the projected pavement condition and future plans to reconstruct the roadway, an overlay is an appropriate alternative and less costly.



# Executive Capital Improvement Plan 2023

**Project Name: Highway – STH 76 to 45 to N CTY Line Road**





# Executive Capital Improvement Plan 2023

Project Name --->> Parks -WauKau Creek Dam								
ANTICIPATED PROJECT COSTS AND SOURCES OF FUNDS:								
	Prior years	2023	2024	2025	2026	2027	Beyond	Total
<b>PROJECT COST'S</b>								
Planning, Design, Engineering		230,000						230,000
Land Purchase								-
Construction			1,500,000					1,500,000
Equipment								-
Other								-
TOTAL	-	230,000	1,500,000	-	-	-	-	1,730,000
<b>PROJECT FUNDS</b>								
County Funding		230,000	750,000					980,000
Outside funding			750,000					750,000
Operating Tax Levy								-
Previous bonding								-
TOTAL	-	230,000	1,500,000	-	-	-	-	1,730,000

## **Project Description:**

This project will address the needed repairs of the dam area of Waukau Creek. Severe rains have overtopped the dam and washed out the embankments surrounding the dam and pond. This dam protects the water levels in the UIHLEIN Waterfowl Production Refuge up stream and keeps the Carp from migrating upstream into Rush Lake. The embankment will be reinforced to allow for water to spill out of the pond during heavy rain events while also limiting the damage or restoration needed following the heavy rain events. The parking lot will be pulverized and repaved. Site lighting will be added for security. A small parking lot on HWY K will be added for the single track bike trails. The dam's catwalks and railing systems will be replaced to follow ADA requirements and provide much safer access. Two fishing piers will be added and the present one will be repaired.

## **Relationship to Other Projects:**

This project is not associated with any other project or plan.

## **Justification & Alternatives Considered**

The only alternative is to remove the Dam and let the river decide it own course. This Dam regulates the river flow down stream and into a holding pond. This pond is used by the Omro-Rushford Fire Department as a water fill site. It is also a very popular Park for Families and Fishing. The Dam also keeps the water level in the UIHLEIN Waterfowl Production Refuge at a level in which the birds can use this area for a migratory stop over point and nesting area. The critical function of this dam is to prevent Carp and other Rough fish from swimming further upstream into the water shed. Rush lake would be inundated by Carp if this dam failed or was removed.






# Executive Capital Improvement Plan 2023

## National Flood Hazard Layer FIRMette



Figure 1.

88°46'36"W 43°59'50"N



0 250 500 1,000 1,500 2,000 Feet 1:6,000

Basemap: USGS National Map: Orthoimagery: Data refreshed October, 2020

### Legend

SEE FIS REPORT FOR DETAILED LEGEND AND INDEX MAP FOR FIRM PANEL LAYOUT

SPECIAL FLOOD HAZARD AREAS		Without Base Flood Elevation (BFE) Zone A, V, A99
		With BFE or Depth Zone AE, AO, AH, VE, AR
		Regulatory Floodway
OTHER AREAS OF FLOOD HAZARD		0.2% Annual Chance Flood Hazard, Areas of 1% annual chance flood with average depth less than one foot or with drainage areas of less than one square mile Zone X
		Future Conditions 1% Annual Chance Flood Hazard Zone X
		Area with Reduced Flood Risk due to Levee. See Notes, Zone X
		Area with Flood Risk due to Levee Zone D
OTHER AREAS		No SCREEN Area of Minimal Flood Hazard Zone X
		Effective LOMRs
		Area of Undetermined Flood Hazard Zone D
GENERAL STRUCTURES		Channel, culvert, or Storm Sewer
		Levee, Dike, or Floodwall
OTHER FEATURES		20.2 Cross Sections with 1% Annual Chance
		17.8 Water Surface Elevation
		Coastal Transect
		Base Flood Elevation Line (BFE)
		Limit of Study
		Jurisdiction Boundary
MAP PANELS		Digital Data Available
		No Digital Data Available
		Unmapped

This map complies with FEMA's standards for the use of digital flood maps if it is not void as described below. The basemap shown complies with FEMA's basemap accuracy standards

The flood hazard information is derived directly from the authoritative NFHL web services provided by FEMA. This map was exported on 6/14/2022 at 11:51 AM and does not reflect changes or amendments subsequent to this date and time. The NFHL and effective information may change or become superseded by new data over time.


This map image is void if the one or more of the following map elements do not appear: basemap imagery, flood zone labels, legend, scale bar, map creation date, community identifiers, FIRM panel number, and FIRM effective date. Map images for unmapped and unmodernized areas cannot be used for regulatory purposes.





# Executive Capital Improvement Plan 2023

**Project Name: Parks – Waukau Creek Dam**



**Waukau Dam**  
Master Plan

Winnebago County, WI  
06.14.2022



SCALE  
0 30' 60' 120'  
CONTour INTERVAL = 5'-0"








# Executive Capital Improvement Plan 2023

Project Name: Parks – Waukau Creek Dam



**Waukau Dam**  
Character Images

Winnebago County, WI  
06.14.2022



SCALE  
0 30' 60' 120'





# Executive Capital Improvement Plan 2023

DATE: 6/14/2022

<b>WAUKAU DAM MASTER PLAN</b> <b>ENGINEER'S ESTIMATE OF PROBABLE COSTS</b> <b>WINNEBAGO COUNTY, WISCONSIN</b> <b>JUNE 2022</b>					
ITEM NO.	ITEM DESCRIPTION	ESTIMATED QUANTITY	UNITS	UNIT PRICE	TOTAL PRICE
<b>SITE</b>					
1.	Mobilization, Bonds, and Insurance	1	LS	\$ 100,000.00	\$ 100,000.00
2.	Erosion Control and Matting	1	LS	\$ 20,000.00	\$ 20,000.00
3.	Turf and Site Restoration	1	LS	\$ 15,000.00	\$ 15,000.00
4.	Unclassified Excavation	1	LS	\$ 30,000.00	\$ 30,000.00
5.	Clearing and Grubbing	1	LS	\$ 25,000.00	\$ 25,000.00
6.	Shoreline Armorment	2,300	SY	\$ 65.00	\$ 149,500.00
7.	Armoflex Matting	2,350	SF	\$ 30.00	\$ 70,500.00
8.	Reinforced Turf	21,750	SF	\$ 10.00	\$ 217,500.00
9.	Site Lighting	1	LS	\$ 25,000.00	\$ 25,000.00
10.	Concrete Sidewalk with Base	3,400	SF	\$ 10.00	\$ 34,000.00
11.	Asphaltic Concrete Pavement	625	TON	\$ 125.00	\$ 78,125.00
12.	Base Course	1,570	TON	\$ 20.00	\$ 31,400.00
13.	Pavement Markings	1	LS	\$ 5,000.00	\$ 5,000.00
14.	Gravel Paths	22,000	SF	\$ 3.50	\$ 77,000.00
15.	Shelter	1	LS	\$ 40,000.00	\$ 40,000.00
16.	Bench w/ Concrete Pad	6	EA	\$ 2,500.00	\$ 15,000.00
17.	Picnic Table	5	EA	\$ 1,500.00	\$ 7,500.00
18.	Removable Bollard	2	EA	\$ 1,500.00	\$ 3,000.00
19.	Signage (Park and Traffic)	1	LS	\$ 5,500.00	\$ 5,500.00
20.	Accessible Fishing Piers	2	EA	\$ 50,000.00	\$ 100,000.00
21.	Repair Existing Pier	1	LS	\$ 15,000.00	\$ 15,000.00
22.	Bike Fix-It Station	1	EA	\$ 4,500.00	\$ 4,500.00
23.	Kiosk	1	EA	\$ 3,000.00	\$ 3,000.00
<b>SUBTOTAL: Items #1 - #23</b>				<b>Subtotal =</b>	<b>\$ 1,068,525.00</b>
<b>DAMS</b>					
24.	Upper Dam - Replace Catwalk/Rail System	1	LS	\$ 25,000.00	\$ 25,000.00
25.	Upper Dam - Add Pedestrian Rail on Approaches to Shield Dropoff	80	LF	\$ 300.00	\$ 24,000.00
26.	Upper Dam - Repair Fish Deterrent	1	LS	\$ 5,000.00	\$ 5,000.00
27.	Lower Dam - Replace Steel Rails	1	LS	\$ 8,000.00	\$ 8,000.00
28.	Lower Dam - Add Pedestrian Rail on Approaches to Shield Drop-Off	80	LF	\$ 300.00	\$ 24,000.00
29.	River Dam - Replace Catwalk/Rail System	1	LS	\$ 25,000.00	\$ 25,000.00
30.	River Dam - Add Pedestrian Rail on Approaches to Shield Drop-Off	80	LF	\$ 300.00	\$ 24,000.00
31.	River Dam - Add Armoflex Matting	1,300	SF	\$ 30.00	\$ 39,000.00
32.	River Dam - Repair Stone Walls	1	LS	\$ 7,500.00	\$ 7,500.00
<b>SUBTOTAL: Items #24- #32</b>				<b>Subtotal =</b>	<b>\$ 181,500.00</b>
				<b>Subtotal Bid=</b>	<b>\$ 1,250,025.00</b>
				<b>20% Contingency =</b>	<b>\$ 250,005.00</b>
				<b>Engineering=</b>	<b>\$ 230,000.00</b>
				<b>Total Project Cost=</b>	<b>\$ 1,730,030.00</b>





# Executive Capital Improvement Plan 2023

Project Name ---> Sheriffs - Jail Camera & Cabling								
ANTICIPATED PROJECT COSTS AND SOURCES OF FUNDS:								
	Prior years	2023	2024	2025	2026	2027	Beyond	Total
<b>PROJECT COST'S</b>								
Planning, Design, Engineering								-
Land Purchase								-
Construction								-
Equipment		350,000						350,000
Other								-
TOTAL	-	350,000	-	-	-	-	-	350,000
<b>PROJECT FUNDS</b>								
County Funding		350,000						350,000
Outside funding								-
Operating Tax Levy								-
Previous bonding								-
TOTAL	-	350,000	-	-	-	-	-	350,000

## Relationship to Other Projects:

This project is not associated with any other project or plan.

## Justification & Alternatives Considered

The Winnebago County Sheriff's Office Jail is an adult correctional facility with a capacity of 355 inmates. The facility provides services for a transient population, which averages fourteen new inmates daily. Currently, there are fifteen glass door isolation cells that are monitored at all times by cameras. These camera-monitored cells are used for a variety of situations such as medical observation and suicide watch. Due to the geographical location of the Winnebago County Jail, the Agency houses a higher number of individuals who require monitoring for mental health concerns. Routinely individuals are housed in the booking area due to our monitored cells being occupied. This along with COVID-19 has put a strain on our ability to assure the safety of those inmates that require continuous monitoring. Since the onset of the pandemic, there have been 250 COVID-19 positive individuals housed in our facility, to include four who were transported for hospitalization. At numerous times during COVID-19 outbreaks, the number of inmates that required medical monitoring outnumbered the amount of medically monitored cells we had available. Additionally, these fifteen camera-monitored cells are supported by the antiquated infrastructure that routinely fails and is at end-of-life. We are requesting an additional thirteen cameras and the infrastructure needed to support them which will create thirteen additional medical monitored cells. We are also requesting an upgrade to the existing camera infrastructure to assure all cameras are reliable and will not fail.

## Project Description:

The Winnebago County Jail is requesting an upgrade to the current surveillance camera system. We are operating with the original cabling from 2003 which is antiquated and beyond end of life. We have had several camera failures multiple times throughout the last two years. This project would replace all of the cabling to the existing 101 cameras inside and outside of the facility. The project would include adding 13 cameras to provide more monitored cells for our growing population with medical and mental health concerns and future needs for COVID-19 outbreaks. The project also includes replacing and installing five 24-port Power Over Ethernet (POE) systems and updated software for the operation of the cameras.



# Executive Capital Improvement Plan 2023

Project Name: Sheriff – Jail Cameras and Cabling

The Winnebago County Jail opened in 2003 and since opening, there have been multiple camera revisions. Currently there are **101** cameras installed throughout the facility.

Today, there is more than one camera that is non-functional.







# Executive Capital Improvement Plan 2023

Project Name: Sheriff – Jail Cameras and Cabling

## CAMERAS

- There are several different cameras located throughout the facility each serving a specific purpose.
- Fisheye Cameras
- Multisensor Cameras
- Mini Dome Cameras
- Corner Cameras





# Executive Capital Improvement Plan 2023

Project Name: Sheriff – Jail Cameras and Cabling

## MASTER CONTROL





# Executive Capital Improvement Plan 2023

Project Name: Sheriff – Jail Cameras and Cabling

## FUTURE CAMERA USE

- CIP project replaces all end of life wiring and other components
- CIP project also adds 13 cameras
  - One camera has been repeatedly recommended to be added by the State of Wisconsin Department of Corrections Jail Inspector
  - 12 additional cameras added to create additional monitored cells for an increasing population with medical issues and mental health concerns





# Executive Capital Improvement Plan 2023

Project Name ----> Sheriffs - Dispatch Console Replacement								
ANTICIPATED PROJECT COSTS AND SOURCES OF FUNDS:								
	Prior years	2023	2024	2025	2026	2027	Beyond	Total
<b>PROJECT COST'S</b>								
Planning, Design, Engineering								-
Land Purchase								-
Construction								-
Equipment		260,000						260,000
Other								-
TOTAL	-	260,000	-	-	-	-	-	260,000
<b>PROJECT FUNDS</b>								
County Funding		260,000						260,000
Outside funding								-
Operating Tax Levy								-
Previous bonding								-
TOTAL	-	260,000	-	-	-	-	-	260,000

## **Project Description:**

Replacement of the existing nine (9) ergonomic dispatch console work stations in the 911 communications center. These positions are staffed 24/7/365, and all components were originally purchased when the building was new (2003). The warranty on this equipment expired in 2008. The existing console work stations are obsolete, and finding replacement parts for repairs has been nearly impossible. This project will replace all components of the dispatch console positions, to include the electronic adjustable furniture console pieces, sit to stand surface heights, adjustable monitor arrays, technology towers, mapping displays, climate controlled panel partitions, task lighting, personal environments, ergonomic seating, active workstations, status indicator lighting, storage, accessory and resource tables; and associated design, delivery, installation, and removal of old components, in a hot swap environment.

## **Relationship to Other Projects:**

This project is not associated with any other project or plan.

## **Justification & Alternatives Considered**

There are no alternatives to replacing these obsolete, outdated, in disrepair console work stations. Ergonomic features must be included, and the dispatch specific technology enhanced design supports multi-system hardware components, to include seven (7) monitors in stacked rows at each position.

One console work station no longer properly functions, as it has been stripped of essential parts to be used to repair broken components on other consoles. Other consoles only have limited functionality remaining. Consideration was given to replacing the workstations piecemeal, or as needed, but that would increase the overall project costs as buying, shipping, and installing the purchase with economy of scale considered will be affected.





# Executive Capital Improvement Plan 2023

Project Name: Sheriff – Dispatch Console Replacement

## What is a Dispatch Console Workstation?

- Flat surface to support computer and monitor components
- Ergonomic features - fully adjustable work surfaces that operate on a single plane
  - ADA compliant controls; foot rest, arm rest, etc.
  - ANSI/HFES 100-2007 - Human Factors Engineering Of Computer Workstations – lift, tilt, clearance, etc.
  - Task lighting, radiant heat, cooling

### E911 Workstations

- Must house very sensitive electronics and CPU units
  - Venting, electrical requirements, cabling housing



# Executive Capital Improvement Plan 2023

Project Name: Sheriff – Dispatch Console Replacement

## Fall 2022

---

All 9 stations must be replaced





# Executive Capital Improvement Plan 2023

Project Name ---> UW Fox Cities - Barlow Planetarium Updates								
ANTICIPATED PROJECT COSTS AND SOURCES OF FUNDS:								
	Prior years	2023	2024	2025	2026	2027	Beyond	Total
<b>PROJECT COST'S</b>								
Planning, Design, Engineering	12,000							12,000
Land Purchase								-
Construction		155,000						155,000
Equipment								-
Other								-
<b>TOTAL</b>	<b>12,000</b>	<b>155,000</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>167,000</b>
<b>PROJECT FUNDS</b>								
County Funding	6,000	77,500						83,500
Outside funding	6,000	77,500						83,500
Operating Tax Levy								-
Previous bonding								-
<b>TOTAL</b>	<b>12,000</b>	<b>155,000</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>-</b>	<b>167,000</b>

## **Project Description:**

Upgrade the Barlow Planetarium that is utilized for instruction and community education programs. Renovation of existing Barlow Planetarium, which was originally constructed in 1998, consists of the following: remove elements that will no longer be necessary, add a light lock, improve guest flow in the lobby area, door replacement, interior ceiling modifications to accommodate the updated equipment, redistribute electrical to accommodate the new projectors and new cove lighting, interior finish updates, and HVAC modifications needed to meet the needs of the new equipment in regards to heating, cooling, humidity, and filtration. This project will accomplish the remodeling necessary for the 1990's technology system to be upgraded. The technology system cost will be covered by the UW Systems Board of Regents, with the counties responsible for the necessary building renovations.

## **Relationship to Other Projects:**

This project is to be funded jointly between Outagamie and Winnebago Counties. Therefore, any decision to proceed with the project will be dependent on the Outagamie County decision on the project. UW Oshkosh would be responsible to provide the funds to replace the projection and audio equipment, as well as office furniture and seating, which is estimated to be approximately \$1,135,000. UWO Buckstaff Planetarium was decommissioned in 2019 since there was no need to have 2 planetariums within 30 miles of each other. Barlow remains the premier experience for NE Wisconsin, currently serving 30,000 visitors per year with a projection to double its annual visitor number once renovated.


## **Justification & Alternatives Considered**

Upon further evaluation of needs, the original placeholder project of the Astronomical Observatory Facility is being redefined to update the Barlow Planetarium. The educational purpose of the Barlow Planetarium is to have a modest facility that will provide astronomy classes for the university and for community educational programs. The current technology within the Barlow Planetarium has become very difficult to maintain, as the current equipment is no longer supported. This renovation is critical to it's future.





# Executive Capital Improvement Plan 2023





# Executive Capital Improvement Plan 2023

Project Name ----> UW Fox Cities - Food Service & Union Facilities								
ANTICIPATED PROJECT COSTS AND SOURCES OF FUNDS:								
	Prior years	2023	2024	2025	2026	2027	Beyond	Total
PROJECT COST'S								
Planning, Design, Engineering	350,000							350,000
Land Purchase								-
Construction		4,418,000						4,418,000
Equipment								-
Other								-
TOTAL	350,000	4,418,000	-	-	-	-	-	4,768,000
PROJECT FUNDS								
County Funding	175,000	2,209,000						2,384,000
Outside funding	175,000	2,209,000						2,384,000
Operating Tax Levy								-
Previous bonding								-
TOTAL	350,000	4,418,000	-	-	-	-	-	4,768,000

## **Project Description:**

Renovate food preparation/storage, kitchen, service area (constructed in 1959 with few improvements since then). Add square footage to union activity/student organization area.

## **Relationship to Other Projects:**

This project is to be funded jointly between Outagamie and Winnebago Counties. Therefore, any decision to proceed with the project will be dependent on the Outagamie County decision on the project. This project is broken into three phases overall. Phase I was the feasibility study to develop optional concepts with cost estimates. Phase II is the development of a final selection of concept into architectural and engineering documentation with final estimates of cost for construction. Phase III will be the finalization of bidding documentation, bidding and construction.

## **Justification & Alternatives Considered**

Existing facilities for food storage, preparation and service have had little improvement since original construction in 1959. Areas are too small to serve the numbers of students and other customers on a daily basis. Existing utilities limit the quality and type of food service equipment to adequately serve campus needs. Additional space is to be added to the existing activity space constructed 1989 to better serve and encourage student participation in organized academic and entertainment interests.





# Executive Capital Improvement Plan 2023







# Executive Capital Improvement Plan 2023



EXISTING SERVING AREA



Proposed Serving Area



# Executive Capital Improvement Plan 2023

Project Name --->> UW Fox Cities - HVAC Controls replacement for Admin & 1300								
ANTICIPATED PROJECT COSTS AND SOURCES OF FUNDS:								
	Prior years	2023	2024	2025	2026	2027	Beyond	Total
PROJECT COST'S								
Planning, Design, Engineering								-
Land Purchase								-
Construction								-
Equipment		88,330						88,330
Other								-
TOTAL	-	88,330	-	-	-	-	-	88,330
PROJECT FUNDS								
County Funding		44,165						44,165
Outside funding		44,165						44,165
Operating Tax Levy								-
Previous bonding								-
TOTAL	-	88,330	-	-	-	-	-	88,330

## **Project Description:**

Replace HVAC controls in the Administrative and 1300 Wings of the complex. This project is to replace the outdated HVAC control system in the administrative and 1300 buildings of the complex.

## **Relationship to Other Projects:**

This project is not associated with any other project or plan.

## **Justification & Alternatives Considered**



# Executive Capital Improvement Plan 2023

Project Name ---> UW Fox Cities - Library Roof Replacement								
ANTICIPATED PROJECT COSTS AND SOURCES OF FUNDS:								
	Prior years	2023	2024	2025	2026	2027	Beyond	Total
<b>PROJECT COST'S</b>								
Planning, Design, Engineering								-
Land Purchase								-
Construction		350,000						350,000
Equipment								-
Other								-
TOTAL	-	350,000	-	-	-	-	-	350,000
<b>PROJECT FUNDS</b>								
County Funding		175,000						175,000
Outside funding		175,000						175,000
Operating Tax Levy								-
Previous bonding								-
TOTAL	-	350,000	-	-	-	-	-	350,000

## **Project Description:**

This project is to repair/replace the Library roof. The Library roof has been studied and is currently being further evaluated to determine the scope of issues involved with the roof and the required level of repair/replacement. The cost is for total replacement, which would be worst case scenario.

## **Relationship to Other Projects:**

This project is to be funded jointly with Outagamie County and, therefore, any decision to proceed will be dependent on the Outagamie County decision on the project.

## **Justification & Alternatives Considered**

The roof on the library has come to the end of it's useful life and is in need of replacement.





# Executive Capital Improvement Plan 2023

Project Name --->> UW Fox Cities - Replace Science Wing Windows								
ANTICIPATED PROJECT COSTS AND SOURCES OF FUNDS:								
	Prior years	2023	2024	2025	2026	2027	Beyond	Total
PROJECT COST'S								
Planning, Design, Engineering								-
Land Purchase								-
Construction		464,100						464,100
Equipment								-
Other								-
TOTAL	-	464,100	-	-	-	-	-	464,100
PROJECT FUNDS								
County Funding		232,050						232,050
Outside funding		232,050						232,050
Operating Tax Levy								-
Previous bonding								-
TOTAL	-	464,100	-	-	-	-	-	464,100

## **Project Description:**

Replace windows in Science wing. This project is to replace the outdated and inefficient windows on the north and south sides of the Science wing with energy efficient units. To accomplish this work, existing cabinetry, electrical, gas and lab equipment will need to be removed and re-installed. Anticipated escalation costs for materials and labor as well as bidding documentation by licensed architect have been added to the opinion of probable construction cost estimate noted in the study.

## **Relationship to Other Projects:**

This project is to be funded jointly between Outagamie and Winnebago Counties. Therefore, any decision to proceed with the project will be dependent on the Outagamie County decision on the project.

## **Justification & Alternatives Considered**

In 2021, Kontext architects were hired to conduct an assessment of the windows and wall assemblies on the North and South facades (see attached). This investigation did include some invasive investigation to determine if we are developing any areas of mold/mildew from the on-going moisture issues.



# Executive Capital Improvement Plan 2023-2027

Cost of Capital Improvement Plan Projects												
		2023 Years Cost		2024 Years Cost		2025 Years Cost		2026 Years Cost		2027 Years Cost		Total
Department	Project Description	County	Other Funding	County	Other Funding	County	Other Funding	County	Other Funding	County	Other Funding	
Airport	Taxiway Alpha (A) Reconstruction - Final Phase	15,000	285,000	175,000	3,325,000							3,800,000
Airport	Replace Plow Truck	140,000										140,000
Facilities	Courthouse Fourth Floor Ceiling Repairs	155,000										155,000
Facilities	JP Coughlin Center Boiler Replacement	10,000		150,000								160,000
Facilities	Courthouse Fall Protection Install	125,000										125,000
Facilities	Facility Masonry Maintenance Program	162,000		162,000		160,000		133,000		160,000		777,000
Facilities	Neenah Human Services Boiler Replacement	10,000		150,000								160,000
Facilities	Park View Fire Alarm Replacement	113,640										113,640
Facilities	Roof Replacement Program	275,624		331,126		238,527		186,592		161,571		1,193,440
Highway	CTH F (Omro - CTH D)	1,626,818										1,626,818
Highway	CTH JJ (CTH CB to STH 76)	929,600										929,600
Highway	CTH P (Midway Road - STH 47)	150,000				1,229,700	5,270,300					6,650,000
Highway	Highway Department Office and Shop Modernization	2,810,000		2,500,000								5,310,000
Highway	CTH II (USH 45 - North Co Line)	1,886,365	450,641									2,337,006
Parks	Repair and improvement of the Waukau Creek Dam	230,000		750,000	750,000							1,730,000
Sheriff	Jail Wiring and Camera	350,000										350,000
Sheriff	Dispatch Console Work Station Replacement	260,000										260,000
UW Fox Cities	UWO-FOX, Barlow Planetarium Updates	77,500	77,500									155,000
UW Fox Cities	UWO-FOX, Food Service and Union Facilities	2,209,000	2,209,000									4,418,000
UW Fox Cities	UWO-FOX, HVAC Controls replacement for Admin and 1300	44,165	44,165									88,330
UW Fox Cities	UWO Fox Cities - Library Roof Replacement	175,000	175,000									350,000
UW Fox Cities	UWO-FOX, Replace Science Wing Windows	232,050	232,050									464,100
Subtotal 2023		11,986,762	3,473,356	4,218,126	4,075,000	1,628,227	5,270,300	319,592	-	321,571	-	31,292,934
Airport	Design & Replace Airport Fire Station					400,000		5,500,000				5,900,000
Airport	Replace Airport Operations Vehicle - 2003 Expedition			50,000								50,000
Airport	Replace Airport Operations Vehicle - 2008 Trailblazer							50,000				50,000
Airport	Replace Large Fire Truck - ARFF					850,000						850,000
Facilities	Courthouse Boiler and Air Conditioning Replacement			25,000		300,000		2,000,000		2,000,000		4,325,000
Facilities	Orrin King Building Window Replacement					34,850		350,000				384,850
Facilities	Courthouse Fifth Floor Remodel									795,000		795,000
Facilities	Sheriff's Office Building Window Replacement							10,000		125,000		135,000
Facilities	Neenah Human Services Covered Entrancer Canopy Install			10,000		100,000						110,000
Facilities	Oshkosh Human Services Entrance Ramp			10,000		150,000						160,000
Facilities	Oshkosh Human Services Covered Entrancer Canopy Install			10,000		100,000						110,000
Facilities	Orrin King Building Window Replacement			34,850		350,000						384,850
Facilities	Orrin King Building Ramp Repair			15,000		150,000						165,000



# Executive Capital Improvement Plan 2023-2027

Cost of Capital Improvement Plan Projects												
		2023 Years Cost		2024 Years Cost		2025 Years Cost		2026 Years Cost		2027 Years Cost		Total
Department	Project Description	County	Other Funding	County	Other Funding	County	Other Funding	County	Other Funding	County	Other Funding	
Highway	CTH N (CTH FF - STH 44)			275,000		1,500,000						1,775,000
Highway	CTH HH (CTH AH - West Co Line)			450,000								450,000
Highway	CTH S (Ryf Rd - STH 116)					867,598	332,402					1,200,000
Highway	CTH E (Oakwood Rd - STH 116)			1,500,000								1,500,000
Highway	West Side Arterial Corridor Study									100,000		100,000
Highway	CTH II (STH 76 - USH 45)			1,400,000								1,400,000
Parks	Shangri La Parking Lot and Site Access			100,000								100,000
Parks	Expo West Drainage/Parking Lot Improvements and Repair			443,254		3,989,282						4,432,536
Parks	Butte des Morts Boat Landing Improvement Project					84,766		529,790	529,790			1,144,346
Parks	Eureka Playground Replacement and Improvements							200,000				200,000
Parks	Shelter 4 and Playground							40,000		750,000		790,000
Parks	Expo Center Maint./Barn F Buildings - Phase 3							176,000		2,024,000		2,200,000
UW Fox Cities	1300 Wing Flooring Replacement							213,400				213,400
UW Fox Cities	Roof Top Unit Replacement for Admin/Library/Science Wings					70,000	70,000					140,000
UW Fox Cities	Roof Top Unit Replacement for Art/Music Wing			15,000	15,000							30,000
UW Fox Cities	Air Conditioning Unit Replacements							70,000	70,000			140,000
UW Fox Cities	Blacktop Repair, Engineering Building							30,000	30,000			60,000
UW Fox Cities	Communication Arts Center Updates			25,000	25,000							50,000
UW Fox Cities	Engineering Study for 1800 Wing Boiler System Replacement			12,500	12,500							25,000
UW Fox Cities	LED Lighting Conversion, Phases 1-3			95,500	95,500	95,500	95,500	95,500	95,500			573,000
UW Fox Cities	Library Flooring Replacement			77,500	77,500							155,000
UW Fox Cities	Parking Lot General Maintenance									30,000	30,000	60,000
UW Fox Cities	Roof Top Unit Replacement for Art/Music Wing			25,000	25,000							50,000
UW Fox Cities	Science Wing Flooring Replacement					101,800	101,800					203,600
UW Fox Cities	Security Upgrades (Card Access and Cameras)			30,000	30,000							60,000
Total Cost 2024-2027		-	-	4,603,604	280,500	9,143,796	599,702	9,264,690	725,290	5,824,000	30,000	30,471,582
Total Cost 2023-2027		11,986,762	3,473,356	8,821,730	4,355,500	10,772,023	5,870,002	9,584,282	725,290	6,145,571	30,000	61,764,516
	CIP 2023 Year Projects											
	CIP 2024-2027 Year Projects											
	Decision on Which Project to keep in Current Year and the other to move to Future Year to stay under \$10M of CIP per Executive. If move Highway project will need to do Mold Remediation on Project Removed Page 61.											





## Projects Removed from the Executive Capital Improvement Plan 2023 - 2027

Cost of Capital Improvement Plan Projects													
Department	Project Description	Prior Cost	2023 Years Cost		2024 Years Cost		2025 Years Cost		2026 Years Cost		2027 Years Cost		Total
			County	Other Funding	County	Other Funding	County	Other Funding	County	Other Funding	County	Other Funding	
Facilities	Courthouse Boiler and Air Conditioning Replacement		25,000		300,000		2,000,000		2,000,000				4,325,000
Facilities	Highway Department Facility Mold Mitigation & Improvements		600,000										600,000
UW Fox Cities	UWO-FOX, Science Rooms, Fume Hood Replacements		205,125	205,125									410,250
UW Fox Cities	UWO Fox Cities, Building and Land Purchase		375,000	375,000									750,000
UW Fox Cities	UWO-FOX, Tennis Courts Removal		93,900	93,900									187,800
Total Cost		-	1,299,025	674,025	300,000	-	2,000,000	-	2,000,000	-	-	-	6,273,050



# Executive Capital Improvement Plan 2023

## Capital Project Status Report

As of 10.31.2022

Project	Resolution #	Approved & First Funded	Authorized Budget	Actual Spent Since Inception	Remaining Funds Available	Status & Completion Timeline
Sheriff Evidence Storage Building / 4008	152-042021	April 2021	1,830,080	2,500	1,827,580	The original budget was approved at \$305,500. \$1,542,580 was added to the project budget in 2022, to include a morgue. Detailed design and bid document development is ongoing. It is anticipated to go out for bid early 2023.
980 Residential Facility / 4009	66-062022	May 2022	1,068,427	-	1,068,427	The original budget was approved at \$1,068,427. The project's detailed design and bid documents are being developed. Site has been surveyed. It will go before the City Planning Review Board and Planning Commission in November, then before City Council in December. It will go out for bid in January with construction to start as soon as the frost is out of the ground.
Courthouse Masonry / 4130	151-042021	April 2021	875,000	459,574	415,426	The original budget was approved at \$875,000. This project is now complete and has come in under budget. The remaining funds will either be returned to the debt service fund or used for another project that requires additional funding from debt service.
District Attorney Remodel / 4131	155-042021	April 2021	220,000	179,932	40,068	The original budget was approved at \$190,000. This project is ongoing and should be complete in December 2022.
Orrin King Roof / 4132	154-042021	April 2021	227,000	139,347	87,653	The original budget was approved at \$211,600. This project is now complete and has come in under budget. The remaining funds will either be returned to the debt service fund or used for another project that requires additional funding from debt service.
USDA Remodel @ Coughlin / 4134	68-062022	May 2022	259,900	-	259,900	The original budget was approved at \$259,900. The project is ongoing as lease negotiations have not been completed. Once the lease is completed and accepted the remodeling work will begin.
UWO-FCC Child Care Center / 4316	225-102019	October 2019	673,424	347,186	326,238	The original budget was approved at \$534,600. Bids came in over budget and \$69,412 was transferred in from the General Fund - undesignated fund balance. The project is 90% complete and should be completed by mid to late December 2022.
Expo Campus Improvements / 4318	140-032021	March 2020	1,789,933	1,704,472	85,461	The original budget was approved at \$1,636,200. The bid has been awarded to Folske Electric and MCC. A general fund undesignated fund balance transfer of \$153,733 was needed for additional costs. The project is 99% complete, waiting on MCC's work to be completed to release their final retainage payment.



# Executive Capital Improvement Plan 2023

## Capital Project Status Report

As of 10.31.2022

Project	Resolution #	Approved & First Funded	Authorized Budget	Actual Spent Since Inception	Remaining Funds Available	Status & Completion Timeline
Grundman Boat Landing Improvements / 4319	276-022022	February 2022	1,976,500	54,824	1,921,676	The original budget was approved at \$185,000 for improvements and renovations to address the insufficient number of parking stalls, site safety, and lack of amenities. In September 2022, \$1,791,500 was added to this project for the construction phase of the project. The project is in the final design phase, looking to go out to bid end of November for construction, and start construction in the spring 2023.
UWO-FCC Science Room Fume Hoods / 4320	295-032022	March 2022	19,580	15,664	3,916	The original budget was approved at \$19,580 for the feasibility study addressing design of necessary system improvements related to the fume hoods in the science wing addition at UWO-Fox Cities Campus. Half of this cost is funded by the General Fund - undesignated fund balance, the other half of the cost will be paid by Outagamie County. This project identified numerous components that were not operational. The components are being repaired. After repair another balancing test will be completed in order to balance and ensure the fume hoods are exhausting the lab air properly. Eplacement of the fume hoods may not be necessary.
UWO-FCC Student Dev/Food Service / 4321	42-042022	April 2022	341,400	-	341,400	The original budget was approved at \$341,400 to perform design and engineering services of the Food Service and Student Development areas of UWO-Fox Cities Campus. Half of this cost is funded by the General Fund - undesignated fund balance, the other half of the cost will be paid by Outagamie County. Request for Proposals (RFP) for design services will be released the end of November 2022. Original UWO schedule had the design services being awarded by the end of December, but may be pushed out due to the holidays.
Community Parks Parking Lot Improv / 4322	49-052022	May 2022	750,000	509,634	240,366	The original budget was approved at \$750,000. This project is ongoing and will finish in 2023.
Parks Expo Equine Complex Improv / 4323	55-052022	April 2022	127,000	104,308	22,692	The original budget was approved at \$127,000 for the Sunnyview Expo LED lights, blacktop repair and gutter installation. The asphalt and LED lights are complete. Gutters will be installed in 2023. The Equine Complex repairs were presented in the Capital Improvement Plan 2022-2026 for \$190,000. Roughly \$63,000 for insulation work at the complex will be presented later in the year.





# Executive Capital Improvement Plan 2023

## Capital Project Status Report

As of 10.31.2022

Project	Resolution #	Approved & First Funded	Authorized Budget	Actual Spent Since Inception	Remaining Funds Available	Status & Completion Timeline
UWO-FCC Barlow Planetarium / 4324	115-102022	October 2022	12,000	-	12,000	The original budget was approved at \$12,000 for the Barlow Planetarium renovation feasibility study. 50% of the cost is reimbursed by Outagamie County.
UWO-FCC Blacktop Repairs / 4325	116-102022	October 2022	80,000	-	80,000	The original budget was approved at \$80,000 for the main entrance and parking lot repairs. 50% of the cost is reimbursed by Outagamie County.
UWO-FCC Parking Lots Maintenance / 4326	117-102022	October 2022	43,000	-	43,000	The original budget was approved at \$43,000 for crack fill, seal coat, and re-stripe the area in front of the UW-Platteville Engineering Building and the two North parking lots of the campus. 50% of the cost is reimbursed by Outagamie County.
Redundant Fiber Loop / 4517	73-062022	June 2022	75,000	-	75,000	The original budget was approved at \$75,000 for engineering work for creating a backup for network traffic and internet connectivity. The engineering phase for the fiber loop is about 50-60% completed. They are working on permits and documents to be ready by the end of the year so bidding on the install can be done early 2023. Obtaining the actual fiber will be the longest lead time for the installation phase. If estimates stay on track, we feel the install would be done by Fall 2023.
CTH A - Indian Point to CTH GG / 4701	50-092016 & 259-032018 & 119-032019	September 2016	3,468,000	954,899	2,513,101	The original budget for project costs was approved at \$4.2 million, \$200,000 was added by resolution March 2018 and \$420,000 was added by resolution April 2019. Design 100% complete, right of way acquisition 100% complete, construction is 100% complete. Project is being managed by WisDOT and has received \$3.4 million in state / federal funds. State invoicing is slow, it will take several years before all WisDOT invoicing has been received. \$474,000 has been transferred out.
CTH A - CTH GG to C-Neenah Mill / 4702	49-052022	May 2022	500,000	531,124	(31,124)	The original budget was approved at \$500,000. Construction is complete. Capital project transfers will be done later in the year.
CTH AP Road Diet / 4720	49-052022	May 2022	150,000	10,037	139,963	The original budget was approved at \$150,000. This project is in the design phase.



# Executive Capital Improvement Plan 2023

## Capital Project Status Report

As of 10.31.2022

Project	Resolution #	Approved & First Funded	Authorized Budget	Actual Spent Since Inception	Remaining Funds Available	Status & Completion Timeline
CTH CB - Shady Ln to American Dr / 4736	114-012021	January 2021	300,000	225,489	74,511	The original budget was approved at \$300,000. This project is in construction phase and will be complete this fall.
CTH CB CTH JJ Roundabout / 4738	268-012020	January 2020	2,300,000	1,356,509	943,491	The original budget was approved at \$300,000. The project was awarded \$1,000,000.00 in MLS funding which will be applied toward construction. This is a joint project between the county and the City of Neenah with the city paying 50% of design and construction costs. Design complete. Construction is complete.
CTH FF and Zoar Road / 4782	49-052022	May 2022	100,000	-	100,000	The original budget was approved at \$100,000. This project is in the design phase.
CTH G - CTH T to USH 45 / 4798	49-052022	May 2022	810,000	1,312,495	(502,495)	The original budget was approved at \$810,000. Construction is complete and project came in over budget. Capital project transfers will be done later in the year.
CTH I - Ripple Ave to Waukau Ave / 4803	114-012021	January 2021	400,000	9,471	390,529	The original budget was approved at \$400,000. This project is in the design phase.
CTH II - CTH CB to Clayton Ave / 4817	114-012021	January 2021	665,000	79,324	585,676	The original budget was approved at \$665,000. This project was postponed to 2022 and will be carried over into 2023.
CTH P - STH 47 to Midway Rd / 4885	114-012021	January 2021	780,000	24,149	755,851	The original budget was approved at \$780,000. This project is in early concept design phase.
CTH T - Convert Pioneer Rd to CTH T / 4914	114-012021	January 2021	1,100,000	1,181,289	(81,289)	The original budget was approved at \$100,000 in January 2021. An additional \$1,000,000 was added in May 2022 and the project is in the construction phase.
CTH T - CTH II to Grandview Rd / 4916	268-012020	January 2020	1,075,000	293,890	781,110	The original budget was approved at \$275,000. This project is in the construction phase.
CTH Y - STH 76 to 41 and T to 45 / 4922	114-012021	January 2021	700,000	270,868	429,132	The original budget was approved at \$700,000. This project is in construction phase and will be complete this fall.
Taxiway B Reconstruction Phase I / 5007	158-42015	April 2015	6,500,000	2,467,971	4,032,029	The original budget was approved at \$6,500,000. The project is complete, but the Airport is waiting on the Bureau of Aeronautics to close out grant. The remaining \$4M is federal and state share costs. These are treated as capital contributions on our financials.



# Executive Capital Improvement Plan 2023

## Capital Project Status Report

As of 10.31.2022

Project	Resolution #	Approved & First Funded	Authorized Budget	Actual Spent Since Inception	Remaining Funds Available	Status & Completion Timeline
Airport Terminal Replacement / 5008	257-12016	January 2016	7,400,000	3,816,757	3,583,243	The original budget was approved for \$600,000 for an Architect & Engineer. \$1.1 million was added in December 2018. \$5.7 million was added in December 2019. Bids came in lower at around \$1,500,000 under budget. The project is complete, but the Airport is waiting on the Bureau of Aeronautics to close out grant. The remaining \$3.5M is federal and state share costs. These are treated as capital contributions on our financials.
Taxiway B Reconstruction Phase II / 5010	276-32016	March 2016	4,400,000	1,657,452	2,742,548	The original budget was approved at \$4.4 million. The project is complete, but the Airport is waiting on the Bureau of Aeronautics to close out grant. The remaining \$2.7M is federal and state share costs. These are treated as capital contributions on our financials.
Taxiway A Reconstruction / 5011	147-052019	May 2019	10,515,000	429,203	10,085,797	The original budget was approved at \$10.5 million, of this \$9.975 million was state and federal funding. \$429,203 is the County paid portion of the project (5%), 90% is paid for by the FAA, and 5% by the State. The project work has been finished. Once a final report is received from the Bureau of Aeronautics, the amount of the project to be finalized in our fixed asset system will be just over \$8 million.
Aviation Park Taxiway / 5012	212-092019	September 2019	495,000	464,197	30,803	The original budget was approved at \$450,000. \$45,000 was transferred in from fund balance in December 2019. The project is complete, but the Airport is waiting on the Bureau of Aeronautics to close out grant.
T-Hangar Facilities (20) / 5013	70-062022	June 2022	4,300,000	-	4,300,000	This project was initially started as a capital outlay budgeted item in 2020 for \$116,603 which was carried over to 2021 and into 2022. In 2022, the capital outlay budget was reduced to \$88,603. As of 10/31/2022, \$70,113.03 has been paid to the WI DOT for this project. Once the capital outlay budget has been spent, the expenses will begin going towards the \$4.3M capital project of which \$1.3M is grant assistance provided by the Wisconsin Bureau of Aeronautics (BOA).





# Executive Capital Improvement Plan 2023

## Capital Project Status Report

As of 10.31.2022

Project	Resolution #	Approved & First Funded	Authorized Budget	Actual Spent Since Inception	Remaining Funds Available	Status & Completion Timeline
PVHC Ancillary Building / 5054	285-032020	March 2020	1,349,000	969,726	379,274	The original budget was approved at \$50,000 to set up the design work. In June 2020, \$699,000 was added to the project. Bids were received on 9/8/2021 and were over the project budget. Additional funding of \$600,000 was approved in November. The project is now in the construction phase.
Highway Parking Lot / 5073	268-012020	January 2020	700,000	628,959	71,041	The original budget was approved at \$350,000 for Phase 1. Phase 1 is complete. An additional \$350,000 was added for Phase 2 in February 2021. Phase 2 is near completion.
Highway Building Upgrades / 5075	50-052022	May 2022	300,000	8,186	291,814	The original budget was approved at \$300,000. This project is in construction phase.
Total			<u>58,675,244</u>	<u>20,209,437</u>	<u>38,465,807</u>	



# Executive Capital Improvement Plan 2023

## WINNEBAGO COUNTY

### OUTSTANDING INDEBTEDNESS - ALL

(Includes Solid Waste and Highway Debt because they are included in Debt Limit Calculations)

	ISSUE DATE	MATURITY DATE	NET EFFECTIVE INTEREST RATE	12/31/2022 OUTSTANDING DEBT (Projected)	2023 PRINCIPAL PAID	2023 NEW DEBT	12/31/2023 OUTSTANDING DEBT (Projected)
<b>Notes:</b>							
General Obligation Notes Series 2010B	11/19/10	04/01/2020	3.7100%	-	-	-	-
State of Wisconsin Trust Fund Loan Series 2010C	11/22/10	03/15/2025	5.2500%	388,673	94,566	-	294,106
State of Wisconsin Trust Fund Loan Series 2010D	12/15/10	03/15/2020	5.0000%	-	-	-	-
General Obligation Notes Series 2012A Refunding	03/15/12	04/01/2020	1.6100%	-	-	-	-
General Obligation Notes Series 2015A	11/08/15	04/01/2025	2.7000%	1,370,000	445,000	-	925,000
General Obligation Notes Series 2016A	Nov 2016	04/01/2026	1.8100%	635,000	155,000	-	480,000
General Obligation Notes Series 2017A	Nov 2017	04/01/2027	1.8474%	4,090,000	775,000	-	3,315,000
General Obligation Notes Series 2018A	Nov 2018	04/01/2028	2.7893%	4,140,000	625,000	-	3,515,000
General Obligation Notes Series 2019A	Nov 2019	04/01/2029	2.0674%	5,450,000	710,000	-	4,740,000
General Obligation Notes Series 2020A	Nov 2020	04/01/2030	1.1510%	2,270,000	850,000	-	1,420,000
General Obligation Notes Series 2021A	Nov 2021	04/01/2022	0.3900%	-	-	-	-
<b>NEW ISSUES - FALL 2022:</b>							
General Obligation Notes Series 2022A	Nov 2022	04/01/2032	Unknown	6,000,000	4,315,000	-	1,685,000
		<b>GRAND TOTALS</b>		<b>\$ 24,343,673</b>	<b>\$ 7,969,566</b>	<b>\$ -</b>	<b>\$ 16,374,106</b>



# Executive Capital Improvement Plan 2023


Winnebago County

Future Financing Plan: 2022 - 2026

BAIRD

LEVY YEAR	YEAR DUE	EXISTING DEBT SERVICE	EXISTING MILL RATE (A)	Levy Supported CIP \$6,000,000 - General Obligation Promissory Notes - FINAL Dated: November 10, 2022				Levy Supported Future Borrowings \$10,000,000 G.O. Notes Dated: 10/1/23 \$10,000,000 G.O. Notes Dated: 10/1/24 \$10,000,000 G.O. Notes Dated: 10/1/25 \$10,000,000 G.O. Notes Dated: 10/1/26				COMBINED DEBT SERVICE	COMBINED MILL RATE (A)	IMPACT OVER PRIOR YEAR	YEAR DUE
				PRINCIPAL (4/7)	INTEREST (4/7 & 10/7) 7YC = 3.80%	LESS: BID PREMIUM	TOTAL	Est. AVG = 4.00%	Est. AVG = 4.00%	Est. AVG = 4.00%	Est. AVG = 4.00%				
2021	2022	Actual Levy \$8,197,000	\$0.54									Actual Levy \$8,197,000	\$0.54		2022
2022	2023	\$4,092,803	\$0.24	\$4,315,000	\$153,918	(\$34,781)	\$4,434,138					\$8,526,940	\$0.51	(\$0.03)	2023
2023	2024	\$4,085,028	\$0.24	\$155,000	\$73,975		\$228,975	\$4,486,600				\$8,800,603	\$0.51	\$0.00	2024
2024	2025	\$4,104,465	\$0.23	\$160,000	\$66,100		\$226,100	\$772,200	\$3,898,600			\$9,001,365	\$0.51	\$0.00	2025
2025	2026	\$3,644,153	\$0.20	\$170,000	\$57,850		\$227,850	\$769,800	\$850,100	\$3,717,300		\$9,209,203	\$0.51	\$0.00	2026
2026	2027	\$3,481,233	\$0.19	\$180,000	\$49,100		\$229,100	\$771,500	\$850,400	\$877,100	\$3,291,000	\$9,500,333	\$0.51	\$0.00	2027
2027	2028	\$2,607,075	\$0.14	\$185,000	\$39,975		\$224,975	\$772,200	\$849,700	\$876,600	\$933,700	\$6,264,250	\$0.33	(\$0.18)	2028
2028	2029	\$1,846,800	\$0.09	\$195,000	\$30,475		\$225,475	\$771,900	\$852,900	\$875,100	\$931,600	\$5,503,775	\$0.28	(\$0.05)	2029
2029	2030	\$984,750	\$0.05	\$205,000	\$21,500		\$226,500	\$770,600	\$850,000	\$872,600	\$933,400	\$4,637,850	\$0.23	(\$0.05)	2030
2030	2031			\$215,000	\$13,100		\$228,100	\$773,200	\$851,000	\$874,000	\$934,000	\$3,660,300	\$0.18	(\$0.05)	2031
2031	2032			\$220,000	\$4,400		\$224,400	\$769,700	\$850,800	\$874,200	\$933,400	\$3,652,500	\$0.17	(\$0.01)	2032
2032	2033							\$770,100	\$849,400	\$873,200	\$931,600	\$3,424,300	\$0.16	(\$0.01)	2033
2033	2034								\$851,700	\$875,900	\$933,500	\$2,661,100	\$0.12	(\$0.04)	2034
2034	2035									\$877,200	\$929,100	\$1,806,300	\$0.08	(\$0.04)	2035
2035	2036										\$933,300	\$933,300	\$0.04	(\$0.04)	2036
				\$6,000,000	\$510,393	(\$34,781)	\$6,475,613	\$11,427,800	\$11,554,600	\$11,593,200	\$11,684,600	\$85,779,118			

(A) Mill rate based on 2021 and 2022 Equalized Valuations (TID-OUT) of \$15,082,216,100 and \$16,793,519,300 respectively, with 2.50% annual growth thereafter.








# Executive Capital Improvement Plan 2023



WINNEBAGO COUNTY  
Debt Service Tax Rate - Current and Future Years



Note: Tax rate based on 2021 Equalized Valuation (TID-OUT) of \$15,082,216,100 with 2.5% annual growth.